

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Rogers Operator Well No.: Rogers

LOCATION: Elevation: 1220 Quadrangle: Wallace WV
District: _____ County: Harrison
Latitude: 39.4084 Feet South of 39 Deg. 24 Min. 30.27 Sec.
Longitude: -80.4046 Feet West of -80 Deg. 24 Min. 16.86 Sec.

Well Type: OIL _____ GAS X

Company	<u>West Virginia Land Resources INC</u>	Coal Operator	<u>West Virginia Land Resources INC</u>
	<u>1 Bridge Street</u>	or Owner	<u>1 Bridge Street</u>
	<u>Monongah, WV 26554</u>		<u>Monongah, WV 26554</u>
Agent	<u>David Roddy</u>	Coal Operator	_____
Permit Issued Date	<u>11/22/2024</u>	or Owner	_____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Harrison ss:

Matthew A. Yearsley and Thomas Thrasher being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 13th day of January, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expanding w/ gas blocker	4657'	1250'	4 1/2" casing-1234'	3514'
Expanding	1250'	Surface	7" casing-0	1392'

Description of monument: 77" of 7" casing with company name, well #, API #, and date completed and that the work of plugging and filling said well was completed on the 24th day of January, 2025.

And further deponents saith not. Matthew A Yearsley
Thomas Thrasher



Sworn and subscribe before me this 24th day of February, 2025

My commission expires: August 13, 2029 Kerri A McCormick
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Kenny Willett Title: Inspector **03/07**

RECEIVED
Office of Oil and Gas
MAR 03 2025
WV Department of
Environmental Protection

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

HARRISON COUNTY COAL
Lease or Property Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554

Complete Address
WALLACE, WV
Well Location

Eagle
District
Harrison
County
04486
Well No.
ROGERS
Farm

STATE INSPECTOR SUPERVISING PLUGGING Kenny Willett

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Harrison ss:

MATTHEW A. YEARSLEY and Thomas Thrasher being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources INC well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 13th day of January, 2025 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleansed hole with 3 3/4" stringer down to 4657'. Cemented hole with 195 sacks of Expanding Cement with Gas Blocker from 4657' to 1250'. Tagged top of cement at 1250'. Removed 1234' of 4 1/2" casing from surface to 1234'. Cut 7" casing at 620'. Made a diligent effort to remove 7" casing by pulling 150% over string weight. All Attempts were unsuccessful.		4 1/2" casing	1234'	3514'
		7" casing	0'	1392'
<u>Cemented hole from 1250' to surface as follows:</u> Cemented hole from 1250' to surface with 215 sacks of Expanding Cement. Cement did Circulate at surface. A total of 410 sacks of cement was used to cement the hole from 4657' to surface.				
<i>Kenny Willett</i> 2/25/25				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	N/A	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 24th day of January, 2025



Matthew A. Yearsley
Matthew A. Yearsley

Thomas Thrasher
Thomas Thrasher

Sworn to and subscribed before me this 24th day of February

Kerry McCormick
Notary Public

My commission expires: August 13, 2029

Permit No. 47-033-04866
Well No. 04866
Latitude: 39° 24' 30.27"N
Longitude: -80° 24' 16.86"W

03/0