

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: G.F. Rogers Operator Well No.: 15103

LOCATION: Elevation: 1341.86' Quadrangle: Wallace WV
District: Eagle County: Harrison
Latitude: 39.4152 Feet South of 39 Deg. 24 Min. 54.76 Sec.
Longitude: -80.3971 Feet West of -80 Deg. 23 Min. 49.76 Sec.

Well Type: OIL GAS X

Company	<u>West Virginia Land Resources INC</u>	Coal Operator	<u>West Virginia Land Resources INC</u>
	<u>1 Bridge Street</u>	or Owner	<u>1 Bridge Street</u>
	<u>Monongah, WV 26554</u>		<u>Monongah, WV 26554</u>
Agent	<u>David Roddy</u>	Coal Operator	<u> </u>
Permit Issued Date	<u>11/22/24</u>	or Owner	<u> </u>

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Harrison ss:


Matthew A. Yearsley and Thomas Thrasher being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 7th day of February, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expanding w/ gas blocker	3715'	1940'	0	3259'
6% Gel Spacer	1940'	1573'	7" casing	1156'
Expanding	1573'	884'		
Expanding	884'	Surface		

Description of monument: 77' of 7" casing with company name, well #, API #, and date completed and that the work of plugging and filling said well was completed on the 19th day of February, 2025.

And further deponents saith not. Matthew A. Yearsley
Thomas Thrasher

Sworn and subscribe before me this 14th day of March, 2025
My commission expires: August 13, 2029 [Signature]
Notary Public



RECEIVED
Office Of Oil and Gas

APR 14 2025

Affidavit reviewed by the Office of Oil and Gas: [Signature] 5/14/2025 Title:

WV Department of
Environmental Protection

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
HARRISON COUNTY COAL
Lease or Property Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
WALLACE, WV
Well Location
EAGLE
District
HARRISON
County
5204
Well No.
G.F. ROGERS
Farm

STATE INSPECTOR SUPERVISING PLUGGING KENNY WILLETT

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of HARRISON ss:

MATTHEW A. YEARSLEY and THOMAS THRASHER being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources INC well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 7th day of February, 2025 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cemented hole from 3715' to 1940' using 140 sacks of Expanding Cement with a gas block additive. Cut 4 1/2" casing at 1360' using wireline. Attempted to pull 4 1/2" casing from surface to 1360' by pulling 150% of string weight. All attempts were unsuccessful. Cut 4 1/2" casing at 1342'. Attempted to pull 4 1/2" casing from surface to 1342' by pulling 150% of string weight. All attempts were unsuccessful. Placed perforations in 4 1/2" casing at 1347' and 1337' using 6 shots at each depth. Left 6" Gel spacer from 1940' to 1573'. Cemented well from 1573' to 884' using 35 sacks of Expanding Cement. Cut 4 1/2" casing at 880'. Attempted to pull 4 1/2" casing from surface to 880' by pulling 150% of string weight. All attempts were unsuccessful. Removed 500' of 4 1/2" casing from surface to 500'. Attempted to pull 7" casing at surface by pulling 150% of string weight. All attempts were unsuccessful. Cemented hole from 884' to surface using 110 sacks of Expandable Cement. Cement did circulate at surface. A total of 285 sacks of cement were used to fill from 3715' to surface.	41/2" casing 7" casing	500' 0'	3259' 1156'	
Coal Seams		Description of Monument		
Pittsburgh	N/A	77" of 7" casing with company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 19th day of February, 2025

And further deponents saith not



Sworn to and subscribed before me this 14th day of March 2025

Matthew A. Yearsley

Matthew A. Yearsley

Thomas Thrasher

Thomas Thrasher

Notary Public

My commission expires:

August 13, 2029

Permit No. 47-033-05204
Well No. 5204
Latitude: 39° 24' 54.76"N
Longitude: -80° 23' 49.76"W

RECEIVED
Office of Oil and Gas

APR 14 2025

WV Department of
Environmental Protection

05/23/2025