

H.HIS
O.96W

Company Hope Natural Gas Co.,
 Address Clarksburg, W. Va.
 Farm J. P. Robey
 Acres 68
 Lease No. 44616 and 44697
 Well (Farm) No. One
 Serial No. 7390
 Elevation (SL) 1019
 Quadrangle Clarksburg W.C.
 County Harrison
 District Sardis
 Engineer W. M. Bowers
 Eng. Reg. No. 900
 Date March 9, 1939
 Scale 1" - 400'

STATE OF WEST VIRGINIA
 Department of Mines
 OIL & GAS DIVISION
 Charleston

WELL LOCATION MAP
 File No. Har-481-A

x Denotes location of well on U. S. Topographic Maps, scale 1 to 62,500, latitude and longitude lines being represented by border lines as shown.

- Denotes one inch spaces on border line of original tracing.

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

394

WELL RECORD

Permit No. 481-A

Oil or Gas Well Gas
(Kind)


Company Hope Natural Gas Company
Address Clarksburg, W. Va.
Farm J. P. Robey Acres 68
Location (waters) Flag Run
Well No. 7390 Elev. 1019
District Sardis County Harrison
The surface of tract is owned in fee by Gilio Steziali
R #1. Address Wilsonburg, W. Va.
Mineral rights are owned by ?
Address _____
Drilling commenced Jan. 8, 1924
Drilling completed Feb. 28, 1924
Date shot 2-29-1924 Depth of shot Gordon
Open Flow /10ths Water in _____ Inch
/10ths Merc. in _____ Inch
Volume _____ Cu. Ft.
Rock Pressure _____ lbs. _____ hrs.
Oil _____ bbls., 1st 24 hrs.
Fresh water 440 feet _____ feet
Salt water 1080 feet _____ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer
13			
10	125	125	Size of
8 1/4	1095	1095	
6 5/8	1483	1483	Depth set
5 3/16			
3			Perf. top
2	2350	2350	Perf. bottom
Liners Used			Perf. top
			Perf. bottom

CASING CEMENTED 10" SIZE 125 No. FT. 1-15-24 Date
125' 10" casing cemented through coal seam.
COAL WAS ENCOUNTERED AT 62 FEET 96 INCHES
_____ FEET _____ INCHES _____ FEET _____ INCHES
_____ FEET _____ INCHES _____ FEET _____ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil Gas or Water	Depth Found	Remarks
Pittsburgh Coal			62	70			
Big Dunkard Sand			435	475	Water	440	
First Salt Sand			750	900			
Second Salt Sand			950	1090	Water	1080	
Maxon Sand			1355	1375			
Big Lime			1425	1480			
Big Injun Sand			1480	1575	Gas	1545	
Gantz Sand			1930	1960			
Fifty Foot Sand			2010	2100	Gas	2037	
Thirty Foot Sand			2115	2135			
Gordon Stray Sand			2210	2280	Gas	2253	
Gordon Sand			2288	2342	Gas	2305-2310	
Fifth Sand			2437	2442			

Original total depth ~~2505~~, originally filled and plugged to present total depth ~~2505~~ 2350



MAY 21 1939

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks

Date 4/26, 1939

APPROVED [Signature], Owner

By [Signature]
(Title) mn