

Wells No 4-5-6 to be abnd.

Company South Penn Oil Co.
 Address 411-15 Ave Pittsburgh, Pa.
 Farm Nancy A Rector
 Tract Area 40 Lease No. 53158
 Well (Farm) No. 4-5-6 Serial No. ---
 Quadrangle Fairmont
 County Harrison
 District Cay
St. Tihler

STATE OF WEST VIRGINIA
 DEPARTMENT OF MINES
 OIL AND GAS DIVISION
 CHARLESTON

WELL LOCATION MAP
 FILE NO. HAR-491-492-493

⋄ Denotes location of well on United States
 Topographic Maps, scale 1 to 62,500, latitude
 and longitude lines being represented

WEST VIRGINIA DEPARTMENT OF MINES
OIL AND GAS DIVISION

Permit No. 124-4

Consolidation Coal Co.,

COAL OPERATOR OR OWNER

Mr. C. L. Chin., Fairmont, W. Va.

ADDRESS

COAL OPERATOR OR OWNER

E. W. Thompson,

LEASER OR PROPERTY OWNER

R. D. No. 2, Shinnston, W. Va.

ADDRESS

SOUTH LENO OIL COMPANY,

411 Seventh Avenue,
Pittsburgh, Pa.

COMPLETE ADDRESS

September 21, 1939

WELL AND LOCATION

Clay District

Harrison County

Well No. 5

N. J. Rector

AFFIDAVIT TO BE MADE IN TRIPLICATE AND COPY TO BE MAILED BY REGISTERED MAIL TO THE DEPARTMENT AND COPY TO BE RETURNED BY THE OPERATOR AND THE THIRD COPY (AND EXTRA COPIES IF REQUIRED) TO BE MAILED TO EACH COAL OPERATOR ADDRESS NAMED AT THEIR RESPECTIVE ADDRESSES.

AFFIDAVIT

STATE OF WEST VIRGINIA,

COUNTY OF Harrison

J. F. Black,

SWER

being first duly sworn according to law depose and say that they are experienced in the work of plugging

and filling oil and gas wells and were employed by South Leno Oil Company, well operator and participated in the work of plugging and filling the above well, that said work was commenced on

1st day of August, 1939, and that the well was plugged and filled the following manner:

Manner in which said well was plugged:

Filled hole with aquagel 2365' to 2253'. Cemented 2253' to 2243'.
Filled with aquagel 2243' to 1752'. Cemented 1752' to 1742'. Put
6-5/8" casing, - 1332'. Pulled 8-1/4" casing, - 1181'. Filled with
aquagel 1742' to 1077'. Cement 1077' to 1067'. Filled with aquagel
1067' to 817'. Cemented 817' to 807'. Filled with aquagel 807'
483'. Cemented 483' to 466'. Left hole open to surface.

Manner in which coal was plugged:

Description of monument:

(THE ABOVE DESCRIPTIONS MUST BE IN DETAIL AND IN ACCORDANCE WITH THE PROVISIONS OF SECTION 10, ARTICLE 4, CHAPTER 22 OF THE CODE)

and that the work of plugging and filling said well was completed on the 24th day of August,

1939.

And further deponents swear not

150

[Handwritten signature]

WEST VIRGINIA DEPARTMENT OF MINES
OIL AND GAS DIVISION

411

WELL RECORD

Permit No. *492-A*
498-A
Reinhardt W.C.

Oil or Gas Well **OIL**
(Kind)


Company **South Penn Oil Company**
Address **411 Seventh Ave., Pittsburgh, Pa.**
Farm **Nancy A. Rector** Acres **40**
Location (waters) **Coons Run**
Well No. **5** Elev. **1390.76'**
District **Clay** County **Harrison**
The surface of tract is owned in fee by **E.W. Thompson**
R. D. No. 2 Address **Shinnston, W. Va.**
Mineral rights are owned by **Nancy A. Rector et al**
R. #2, Address **Shinnston, W. Va.**
Drilling commenced **November 9, 1910**
Drilling completed **January 4, 1911**
Date shot **1-9-11** Depth of shot **50 Ft.**
Open Flow /10ths Water in **--** Inch
/10ths Merc. in **--** Inch
Volume **--** Cu. Ft.
Rock Pressure **30** lbs. hrs.
Oil **--** bbls., 1st 24 hrs.
Fresh water **1100** feet
Salt water **1100** feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
16			Callaman Anchor
13			Size of 6-5/8
10	305' 4"		Depth set -
8 1/4	1264'		Perf. top -
6 5/8	1715' 8"		Perf. bottom -
5 3/16			Perf. top -
3			Perf. bottom -
2			Perf. top -
Liners Used			Perf. bottom -

CASING CEMENTED **10"** SIZE **9-18-10** No. FT. **96** Date
COAL WAS ENCOUNTERED AT **280** FEET **96** INCHES
FEET INCHES FEET INCHES
FEET INCHES FEET INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil Gas or Water	Depth Found	Remarks
Pittsburgh Coal			280	288			
Little Dunkard Sand			760	780			
Big Dunkard Sand			840	875			
Gas Sand			1025	1065			
Salt Sand			1100	1240	Water	1110	
Big Lime			1695	1775			
Big Injun			1775	1930	Gas (Small)	1780-1800	
Fifty Foot Sand			2276	2361	Gas Oil	2291-2302 2348-2352	
Total Depth				2363			

551
278
163



Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks

Date June 7, 1939

APPROVED SOUTH PENN OIL COMPANY, Owner

By Clifton Springs Land Agent
(Title)