

LATITUDE 39° 17' 30"



0.30w

0.82w

LONGITUDE 80° 17' 30"

7'5 OGIS topo location

7.5' loc _____ 15' loc _____
(calc.) _____

Company HNG Co (6982)

Farm Park Coal Co.

Quad Clarksburg 7 1/2

County Harrison

District Coal (3)

WELL LOCATION MAP

File No. 033-30773

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

620

WELL RECORD

Permit No. **HAR-773-A**


Oil or Gas Well
(KIND)

Company **Hope Natural Gas Company.**
Address **445 West Main St.**
Farm **Park Coal Company** Acres **887**
Location (waters)
Well No. **6982** Elev. **1031**
District **Coal** County **Harrison**
The surface of tract is owned in fee by
Address
Mineral rights are owned by
Address
Drilling commenced **Purchased well**
Drilling completed
Date Shot From To
With
Open Flow /10ths Water in Inch
/10ths Merc. in Inch
Volume Cu. Ft.
Rock Pressure lbs. hrs.
Oil bbls., 1st 24 hrs.
Fresh water **none recorded** feet feet
Salt water **none recorded** feet feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
16			
13			
10	223	Pulled	Size of
8 1/4	989	Pulled	
6 1/2	1550	Pulled	Depth set
5 3/16			
3			Perf. top
2	2489	2489	Perf. bottom
Liners Used			Perf. top
			Perf. bottom

Annular spaces outside tubing cemented
CASING CEMENTED SIZE No. Ft. Date
to surface- filled solid.
None recorded
COAL WAS ENCOUNTERED AT FEET INCHES
..... FEET INCHES FEET INCHES
..... FEET INCHES FEET INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Sand			190	230			
Sand			420	475			
Sand			555	575			
Salt sands			735	1115			
Maxon sand			1295	1345			
Little Lime			1405	1415			
Big Lime			1440	1500			
Big Injun			1500	1608			
Fifty Foot			1940	2000			
Sand			2015	2075			
Thirty Foot			2138	2163			
Gordon sand			2350	2363			
Fourth Sand			2380	2390			
Fifth sand			2449	2454	Gas	2462	
Total depth				2489			



Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks

Date May 14, 1943, 194

APPROVED Hope Natural Gas Company., Owner

By [Signature] Gen. Sup't.

To Clarkburg

PARK COAL COMPANY NO. 6982 WELL.

773A

Coal District, Harrison County, West Virginia.
By Hope Natural Gas Co., 445 West Main St., Clarksburg, W. Va.
Abandoned under permit Harr-

On 557 acres.

Elevation, 1031'L.

Purchased well.

Casing 10", 223 (pulled); 8 1/2", 989 (pulled); 6 5/8", 1550 (pulled);
tubing 2", 2489.

Annular spaces outside tubing cemented to surface, failed solid.

Abandonment reported to Dept. of Mines May 14, 1943.

Record to RCT from Mrs. Griffith July 13, 1943. Old File No. 620.

	Top.	Bottom.
Sand	190 -	230
Sand	420 -	475
Sand	555 -	575
Salt sand	725 -	1115
Maxon sand	1295 -	1345
Little Lime	1405 -	1415
Big Lime	1440 -	1500
Big Injun	1590 -	1608
Fifty Foot	1940 -	2000
Sand	2015 -	2075
Thirty Foot	2138 -	2163
Gordon sand	2350 -	2363
Fourth Sand	2380 -	2390
Fifth sand (gas #462)	2449 -	2454
Total depth		2489