



STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

639

WELL RECORD

AD 795-A
Permit No. 795-A

Oil or Gas Well **OIL**
(KIND)

Company **South Penn Natural Gas Company**
Address **Union Trust Bldg. Parkersburg, W. Va.**
Farm **G. W. Talkington** Acres **363**
Location (waters) **Middle Run**
Well No. **11** Elev. **1135.24**
District **Sardis** County **Harrison**
The surface of tract is owned in fee by **Reuben White**
Address **Wallace, W. Va.**
Mineral rights are owned by **Inez Talkington et al**
1711 Hamill Ave., Address **Clarksburg, W. Va.**
Drilling commenced **July 1-1904**
Drilling completed **Sept. 2-1904**
Date Shot **See below** From **--** To **--**
With **----**
Open Flow /10ths Water in **--** Inch
/10ths Merc. in **--** Inch
Volume **--** Cu. Ft.
Rock Pressure **5** lbs. **--** hrs.
Oil **----** bbls., 1st 24 hrs.
Fresh water **----** feet **----** feet
Salt water **2805** feet **----** feet


Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer --
13			--
10	321' (Pulled)		Size of --
8 1/4	1500'		--
6 1/2	2185'		Depth set --
5 3/16	2438'		--
3			Perf. top --
2			Perf. bottom --
Liners Used			Perf. top --
Cond. 16'			Perf. bottom --

CASING CEMENTED **--** SIZE **--** No. Ft. **--** Date **--**
COAL WAS ENCOUNTERED AT **950** FEET **60** INCHES
-- FEET **--** INCHES **--** FEET **--** INCHES
-- FEET **--** INCHES **--** FEET **--** INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Pittsburgh Coal			950	955			
Little Dunkard Sand			1340	1370			
Big Dunkard Sand			1440	1450			
Gas Sand			1700	1775			
Salt Sand			1905	2000			
Little Lime			2040	2185			
Pencil Cave			2185	2190			
Big Lime			2190	2240			
Big Injun Sand			2240	2390			
Upper 30' Sand			2660	2700			
Fifty Foot Sand			2800	2830			
					Water	2805	
					Gas	2805	
Lower 30' Sand			2890	2925			
Stray Sand			2960	2990			
Gordon Sand			3005	3032			
					Gas	3019	
					Oil	3019	
Total Depth				3091			

SHOT RECORD:

9 - 2 - 04 - 20 qt.
3 - 19 - 09 - 30 "
10 - 31 - 16 - 40 "
7 - 9 - 35 - 40 " - Gordon



Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks

Date December 23, 1943., 194

APPROVED SOUTH PENN NATURAL GAS COMPANY, Owner

By *Edw. E. Spang* Land Agent.
(Title)