





659

STATE OF WEST VIRGINIA  
DEPARTMENT OF MINES  
OIL AND GAS DIVISION

WELL RECORD

Permit No. 807-A

Oil or Gas Well  
(KIND)

Company.....Hope Natural Gas Company.  
Address.....445 West Main St. Clarkaburg, W. Va.  
Farm.....J. T. Swiger. Acres. 68  
Location (waters).....  
Well No.....3029 Elev. 1322  
District.....Sardin County Harrison  
The surface of tract is owned in fee by.....  
Address.....  
Mineral rights are owned by.....  
Address.....  
Drilling commenced.....June 17, 1913  
Drilling completed.....July 26, 1913  
Date Shot..... From..... To.....  
With.....  
Open Flow /10ths Water in..... Inch  
/10ths Merc. in..... Inch  
Volume..... Cu. Ft.  
Rock Pressure..... lbs..... hrs.  
Oil..... bbls., 1st 24 hrs.  
Fresh water..... none recorded feet..... feet  
1390  
Salt water..... feet..... feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer.....
18			
10	543	543	Size of.....
8 1/4	1545	1545	
6 1/2	1906	1906	Depth set.....
5 3/16	2575	2575	
3			Perf. top.....
2			Perf. bottom.....
Liners Used			Perf. top.....
4 1/2 x 4	162	162	Perf. bottom.....


Not cemented

CASING CEMENTED..... SIZE..... No. Ft..... Date.....  
COAL WAS ENCOUNTERED AT..... 473 FEET..... 84 INCHES  
..... FEET..... INCHES..... FEET..... INCHES  
..... FEET..... INCHES..... FEET..... INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
	Pittsburgh	Coal	473	480			
	Little Dunkard		850	935			
	Big Dunkard		1000	1050			
	Gas sand		1180	1270			
	First Salt		1295	1315			
	Second Salt		1340	1425	water	1390	
	Maxon		1735	1800	gas	1755	
	Pencil cave		1800	1805			
	Big Lime		1805	1900			
	Big Injun		1900	1995	gas	1945	
	Fifty foot		2420	2459			
	Thirty Foot		2536	2556			
	Bordon stray		2566	2577			
	Gordon		2581	2617			
	Sand		2620	2654			
	Fourth		2664	2695	gas	2670	
	5th sand		2824	2826	show oil	2825	
	Total depth			3016			

PARTIAL ABANDONMENT

7/24



Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks

Date May 9, 1944., 194

APPROVED Hope Natural Gas Company., Owner

By [Signature] Gen. Sup't.  
(Title)



STATE OF WEST VIRGINIA  
DEPARTMENT OF MINES  
OIL AND GAS DIVISION

659

WELL RECORD

Refer to 807

Permit No. HAR-207

Gas Well (KIND)

Company **Hope Natural Gas Company.**  
 Address **445 West Main St. Clarksburg, W. Va.**  
 Farm **J.T. Swiger** Acres **68**  
 Location (waters) \_\_\_\_\_  
 Well No. **3029** Elev. **1322**  
 District **Sardis** County **Harrison**  
 The surface of tract is owned in fee by \_\_\_\_\_  
 Address \_\_\_\_\_  
 Mineral rights are owned by \_\_\_\_\_  
 Address \_\_\_\_\_  
 Drilling commenced **June 17, 1913**  
 Drilling completed **July 26, 1913**  
 Date Shot \_\_\_\_\_ From \_\_\_\_\_ To \_\_\_\_\_  
 With \_\_\_\_\_  
 Open Flow \_\_\_\_\_ /10ths Water in \_\_\_\_\_ Inch  
 \_\_\_\_\_ /10ths Merc. in \_\_\_\_\_ Inch  
 Volume \_\_\_\_\_ Cu. Ft.  
 Rock Pressure \_\_\_\_\_ lbs. \_\_\_\_\_ hrs.  
 Oil \_\_\_\_\_ bbls., 1st 24 hrs.  
 Fresh water **none recorded** feet  
 Salt water **1390** feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer
13			
10	<b>543</b>	<b>543</b>	Size of
8 1/4	<b>1545</b>	<b>1545</b>	
6 3/8	<b>1906</b>	<b>80</b>	Depth set
5 3/16	<b>2575</b>	<b>Pulled</b>	
3			Perf. top
2			Perf. bottom
Liners Used			Perf. top
<b>4 1/2 x 4</b>	<b>162</b>	<b>Pulled</b>	Perf. bottom

**Not cemented**  
 CASING CEMENTED \_\_\_\_\_ SIZE \_\_\_\_\_ No. Ft. \_\_\_\_\_ Date \_\_\_\_\_  
 COAL WAS ENCOUNTERED AT **473** FEET **84** INCHES  
 \_\_\_\_\_ FEET \_\_\_\_\_ INCHES FEET \_\_\_\_\_ INCHES  
 \_\_\_\_\_ FEET \_\_\_\_\_ INCHES FEET \_\_\_\_\_ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
<b>WELL HAS BEEN PARTIALLY ABANDONED</b>							
Pittsburgh Coal			<b>473</b>	<b>480</b>			
Little Dunkard			<b>850</b>	<b>935</b>			
Big Dunkard			<b>1000</b>	<b>1050</b>			
Gas sand			<b>1180</b>	<b>1270</b>			
First Salt			<b>1295</b>	<b>1315</b>			
Second Salt			<b>1340</b>	<b>1425</b>	<b>water</b>	<b>1390</b>	
Maxon sand			<b>1735</b>	<b>1800</b>	<b>gas</b>	<b>1755</b>	
Has been filled to				<b>1810</b>			



