





136

STATE OF WEST VIRGINIA  
DEPARTMENT OF MINES  
OIL AND GAS DIVISION

WELL RECORD

Permit No. HAR-1117A


Oil or Gas Well (KIND)

Company Hope Natural Gas Company.  
 Address 445 West Main St. Clarksburg, W. Va.  
 Farm Park Coal Company. Acres 607  
 Location (waters) \_\_\_\_\_  
 Well No. 6980 Elev. 1053  
 District Coal County Harrison  
 The surface of tract is owned in fee by \_\_\_\_\_  
 Address \_\_\_\_\_  
 Mineral rights are owned by \_\_\_\_\_  
 Address \_\_\_\_\_  
 Drilling commenced \_\_\_\_\_  
 Drilling completed February 1929  
 Date Shot \_\_\_\_\_ From \_\_\_\_\_ To \_\_\_\_\_  
 With \_\_\_\_\_  
 Open Flow \_\_\_\_\_ /10ths Water in \_\_\_\_\_ Inch  
 \_\_\_\_\_ /10ths Merc. in \_\_\_\_\_ Inch  
 Volume \_\_\_\_\_ Cu. Ft.  
 Rock Pressure \_\_\_\_\_ lbs. \_\_\_\_\_ hrs.  
 Oil \_\_\_\_\_ bbls., 1st 24 hrs.  
 Fresh water \_\_\_\_\_ feet \_\_\_\_\_ feet  
 Salt water 600 feet \_\_\_\_\_ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer _____
13			
10	<b>145</b>	<b>145</b>	Size of _____
8 1/4	<b>821</b>	<b>821</b>	
6 5/8	<input checked="" type="checkbox"/> <b>1476</b>	<b>1476</b>	Depth set _____
5 3/16	<input checked="" type="checkbox"/> <b>2180</b>	<b>2180</b>	
3			Perf. top _____
2			Perf. bottom _____
Liners Used			Perf. top _____
			Perf. bottom _____

CASING CEMENTED 10" SIZE No. Ft. \_\_\_\_\_ Date \_\_\_\_\_  
no record  
 COAL WAS ENCOUNTERED AT 8 FEET 24 INCHES  
 \_\_\_\_\_ FEET \_\_\_\_\_ INCHES FEET \_\_\_\_\_ INCHES  
 \_\_\_\_\_ FEET \_\_\_\_\_ INCHES FEET \_\_\_\_\_ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
<b>Pittsburg Coal</b>			<b>8</b>	<b>10</b>			
<b>Little Dunkard</b>			<b>232</b>	<b>232</b>			
<b>Big Dunkard</b>			<b>400</b>	<b>415</b>			
<b>Gas sand</b>			<b>445</b>	<b>505</b>			
<b>Sand</b>			<b>600</b>	<b>630</b>	<b>water</b>	<b>600</b>	
<b>Mazon</b>			<b>1315</b>	<b>1335</b>			
<b>Little Line</b>			<b>1435</b>	<b>1445</b>			
<b>Pond 1 cave</b>			<b>1445</b>	<b>1459</b>			
<b>Big Line</b>			<b>1459</b>	<b>1525</b>			
<b>Big Injun</b>			<b>1525</b>	<b>1625</b>			
<b>Fifty foot</b>			<b>1950</b>	<b>2016</b>			
<b>Thirty foot</b>			<b>2022</b>	<b>2154</b>			
<b>Fourth</b>			<b>2410</b>	<b>2430</b>	<b>gas</b>	<b>2412</b>	
<b>Fifth</b>			<b>2479</b>	<b>2509</b>	<b>gas</b>	<b>2499 2508</b>	
<b>Total depth</b>				<b>2516</b>			



Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks

Date October 21, 1947., 194

APPROVED Hope Natural Gas Company., Owner

By \_\_\_\_\_

(Title)  
*JNS*

Clarksburg

PARK COAL CO. NO. 6980 WELL.

1117A

Coal District, Harrison County, W. Va.  
 By Hope Natural Gas Co., 445 W. Main St., Clarksburg, W. Va.  
 Abandoned under permit Har-.....-A7  
 On 887 acres.  
 Elevation, 1053' L.  
 Drilling completed February 1920.  
 Salt water at 600'.  
 10" casing, 145'; 8 1/2", 321'; 6 3/4", 1476'; 5", 2180'; all left in.  
 10" casing cemented.  
 Coal was encountered at 8-10'.  
 Gas well. Abandonment under permit Har-.....-A7  
 Abandonment reported to Dept. of Mines Oct. 21, 1947.  
 Record to RGT from Mrs. Griffith March 24, 1948. Old File No. 938.

	Top.	Bottom.
Pittsburgh Coal	8	10
Little Dunkard Sand	232	252
Big Dunkard Sand	400	415
Gas Sand	445	505
Sand (water, 600')	600	620
Maxton Sand	1315	1355
Little Lime	1435	1445
Pencil Cove	1445	1459
Big Lime	1459	1525
Big Injun Sand	1525	1625
Fifty-foot Sand	1950	2016
Thirty-foot Sand	2028	2154
Fourth Sand (gas, 2412')	2410	2420
Fifth Sand (gas, 2499-2503')	2479	2509
Total depth		2516