



1140

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

WELL RECORD


Permit No. 1332-A Oil or Gas Well _____ (KIND)

Company Hope Natural Gas Company.
 Address 445 West Main St. Clarksburg, W. Va.
 Farm Amelia M. Robinson Acres 137
 Location (waters) _____
 Well No. 394 Elev. 915
 District Eagle County Harrison
 The surface of tract is owned in fee by _____
 Address _____
 Mineral rights are owned by _____
 Address _____
 Drilling commenced May 15, 1903
 Drilling completed June 22, 1903
 Date Shot _____ From _____ To _____
 With _____
 Open Flow _____ /10ths Water in _____ Inch
 _____ /10ths Merc. in _____ Inch
 Volume _____ Cu. Ft.
 Rock Pressure _____ lbs. _____ hrs.
 Oil _____ bbls., 1st 24 hrs.
 Fresh water none recorded feet _____ feet
 Salt water none recorded feet _____ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer _____
13			
10	221	Pulled	Size of _____
8 1/4	894	Pulled	
6 5/8	1255	1255	Depth set _____
5 3/16	2019	2019	
3			Perf. top _____
2	2288	2288	Perf. bottom _____
Liners Used _____			Perf. top _____
			Perf. bottom _____

CASING CEMENTED _____ SIZE _____ No. Ft. _____ Date _____
 COAL WAS ENCOUNTERED AT 255 FEET 36 INCHES
 _____ FEET _____ INCHES FEET _____ INCHES
 _____ FEET _____ INCHES FEET _____ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Little Dunkard			225	255			
Coal			255	258			
Dunkard			335	390	(Circled mark)		
Gas sand			645	845			
Big Lime			1205	1260			
Big Injun			1260	1384			
Fifty foot			1725	1750			
Gordon stray			1820	1850			
Gordon			1860	1890			
Sand			2082	2099	gas	?	
Fourth			2130	2140	gas oil	2132	
Fifth			2238	2265	gas	2246	
Total depth				2288			



AMELIA M. ROBINSON NO. 394 WELL.

Eagle District, Harrison County, W. Va.

By Hope Natural Gas Co., 445 W. Main St., Clarksburg, W. Va.

Abandoned under permit No.-----AT

On 137 acres.

Elevation, 915' L.

Drilling commenced May 15, 1903; completed June 27, 1903.

No water recorded.

10" casing, 221' (pulled); 8½", 894' (pulled); 6½", 1255'; 5" casing, 2019';
2" tubing, 2288'.

Casing not cemented.

Coal was encountered at 255-258'.

Gas well. Abandonment reported to Dept. of Mines April 25, 1949.

Record to RCT from Mrs. Griffith July 10, 1949. Old File No. 1140.

	Top.	Bottom.
Little Burkard Sand	225	- 255
Coal	255	- 258
Burkard Sand	335	- 390
Gas Sand	645	- 845
Big Lime	1205	- 1260
Big Injun Sand	1260	- 1384
Fifty-foot Sand	1725	- 1750
Garden Stray Sand	1820	- 1850
Garden Sand	1860	- 1890
Sand (gas?)	2082	- 2099
Fourth Sand (gas and oil, 2132')	2130	- 2140
Fifth Sand (gas, 2246')	2238	- 2265
Total depth		2288

1332A