

Surface owned by S.H. Day.
 Address: Mr. S.H. Day, R.F.D. No. 1, Bristol, W. Va.
 Coal owned by Willis G. Tetrick, Jr. et al.
 Address: Mr. Willis G. Tetrick, Jr. P.O. Box No. 267, Clarksburg, W. Va.

New Location
 Drill Deeper
 Abandonment On 800 Map N39. Sqs. S7 E 6.

Company Raad Supply Co.
 Address Salem, W. Va.
 Farm James F. Dye
 Tract _____ Acres 203⁸⁴ Lease No. _____
 Well (Farm) No. 4 Serial No. _____
 Elevation (Spirit Level) Floor - 1352.90
Ground - 1351.90
 Quadrangle Centerpoint
 County Harrison District Ten Mile
 Engineer Elsworth Haines
 Engineer's Registration No. 2221
 File No. _____ Drawing No. _____
 Date July 2nd, 1951. Scale 1" = 800 Feet

STATE OF WEST VIRGINIA
 DEPARTMENT OF MINES
 OIL AND GAS DIVISION
 CHARLESTON

WELL LOCATION MAP
 FILE NO. HAR-1488-A

+ Denotes location of well on United States Topographic Maps, scale 1 to 62,500, latitude and longitude lines being represented by border lines as shown.
 - Denotes one inch spaces on border line of original tracing.



STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

1287

WELL RECORD

Permit No. HAR-1488-A

Oil or Gas Well _____
(KIND)

Company Reed Supply Company
Address 184 East Main St., Salem, W. Va.
Farm James F. Dye Acres 203.84
Location (waters) Head waters of Grass Run
Well No. 4 Elev. 1351.90
District Ten Mile County Harrison
The surface of tract is owned in fee by Mr. S. H. Day
R. F. D. #1 Address Bristol, W. Va.
Mineral rights are owned by Willis G. Tetric, Jr.
Box 267 Address Clarksburg, W. Va.
Drilling commenced No Record
Drilling completed " "
Date Shot From _____ To _____
With _____

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer
13			
10	606'	None	Size of
8 1/4	1460'	None	
6 1/2	2548'	2548'	Depth set
5 3/16	3045'	3045'	
3			Perf. top
2	3190'	3190'	Perf. bottom
Liners Used			Perf. top
			Perf. bottom

Open Flow /10ths Water in _____ Inch
/10ths Merc. in _____ Inch
Volume _____ Cu. Ft.
Rock Pressure _____ lbs. _____ hrs.
Oil _____ bbls., 1st 24 hrs.
Fresh water _____ feet _____ feet
Salt water _____ feet _____ feet

CASING CEMENTED No SIZE _____ No. Ft. _____ Date _____
COAL WAS ENCOUNTERED AT 1091 FEET 84 INCHES
_____ FEET _____ INCHES FEET _____ INCHES
_____ FEET _____ INCHES FEET _____ INCHES


Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Pittsburgh Coal			1084	1091			
Little Dunkard Sand			1455	1442			
Big Dunkard Sand			1580	1647			
Gas Sand			1670	1739			
Big Lime			2387	2490			
Big Injtm			2490	2595			
Fifty Foot			2934	2969			
Thirty Foot			3035	3065			
Gordon Stray			3083	3140			
Gorden			3165	3185			
Total Depth				3198			



SEP 12 1951



Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
				2732			
			2702	2702			
			2602	2740			
			2522	2032			
			2532	2532			
			2430	2032			
			2402	2430			
			7620	7422			
			7000	7072			
			7422	7422			
			7022	7022			



MEET RECORD

DEPARTMENT OF MINES
STATE OF WEST VIRGINIA

Date Sept 12 1951

APPROVED Road Supply Co., Owner

By J.M. Road Supply Co.
(Title)



JAMES F. DYE NO. 4 WELL.

14342

Fennile District, Harrison County, W. Va.

By Road Supply Co., 1847 E. Main St., Salem, W. Va.

Abandoned under permit Her-.....-A?

On 203.84 acres, on headwaters of Grass Run.

Elevation, 1351.90' L.

Surface owned by S. F. Dry, R. F. D. No. 1, Bristol, W. Va., and
minerals by Willis G. Petrick, Jr., Box 267, Clarksburg, W. Va.

No record of date of completion, etc.

10" casing, 606' (pulled); 8 $\frac{1}{2}$ " , 1460' (pulled); 6 $\frac{1}{2}$ " , 2348'; 5 $\frac{1}{2}$ " , 3045';

2" tubing, 3190', ~~with~~

Casing not cemented.

Coal was encountered at 1084-1091'.

Oil well. Record to Dept. of Mines dated Sept. 12, 1951.

Record to POT from Mrs. Griffith Feb. 29, 1952. Old File No. 1287.

	Top.	Bottom.
Pittsburgh Coal	1084	- 1091
Little Dunkard Sand	1455	- 1442 ?
Big Dunkard Sand	1580	- 1647
Gas Sand	1670	- 1739
Big Lime	2387	- 2490
Big Injun Sand	2490	- 2595
Fifty-foot Sand	2934	- 2969
Thirty-foot Sand	3035	- 3065
Gordon Stray Sand	3083	- 3140
Gordon Sand	3165	- 3185
Total depth		3198