

LATITUDE 39° 20' 00"



0.40 R
1.71 W

LONGITUDE 80° 20' 00"

7.5 OGIS topo location

7.5' loc _____ 15' loc _____
(calc.) _____

Company Delaware Gas Co.

Farm J. F. Allen Heirs #1


Quad Clarksburg 7 1/2

County Harrison

District Eagle (4)

WELL LOCATION MAP

File No. 033-31567



New location
 Drill deeper
 Abandonment

Company DELAWARE GAS CO
 Address CLARKSBURG, WVA
 Farm JAMES F ALLEN
 Tract EAST Area 50.72 Lease No
 Well Code No. 100 Series No

STATE OF WEST VIRGINIA
 DEPARTMENT OF MINES
 OIL AND GAS DIVISION
 CHARLESTON

WELL LOCATION MAP

WEST VIRGINIA DEPARTMENT OF MINES
OIL AND GAS DIVISION

1439

WELL RECORD

Permit No. HAR-1567-A


Oil or Gas Well **-GAS-**
(Kind)

Company **Delaware Gas Company**
 Address **Clarksburg, West Virginia**
 Farm **J. F. Allen Heirs** Acres **190**
 Location (waters) **Lamberts Run**
 Well No. **1** Elev. _____
 District **Eagle** County **Harrison**
 The surface of tract is owned in fee by **Wayne F. Allen**
 Address **Clarksburg, W. Va.**
 Mineral rights are owned by **J. F. Allen Heirs**
 Address _____
 Drilling commenced **December 13, 1910**
 Drilling completed **December 16, 1913**
 Date shot **Deepened to Speechley** Depth of shot _____
 Open Flow /10ths Water in _____ Inch
 /10ths Merc. in _____ Inch
 Volume _____ Cu. Ft.
 Rock Pressure _____ lbs. _____ hrs.
 Oil _____ bbls., 1st 24 hrs.
 Fresh water _____ feet _____ feet
 Salt water _____ feet _____ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer
13			
10		104' 6"	Size of
8 1/4			
6 5/8		1348'	Depth set
5 3/16		2169'	
3			Perf. top
2		3057'	Perf. bottom
Liners Used			Perf. top
			Perf. bottom

CASING CEMENTED _____ SIZE _____ No. FT. _____ Date _____
 COAL WAS ENCOUNTERED AT _____ FEET _____ INCHES
 _____ FEET _____ INCHES _____ FEET _____ INCHES
 _____ FEET _____ INCHES _____ FEET _____ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil Gas or Water	Depth Found	Remarks
Below Pittsburgh Coal							
Little Dunkard			65	405			
Big Dunkard			455	530			
Gas Sand			640	770			
First Salt				990			
					Gas 2225		
					Oil 2227		
Pencil Cave			1300	1310			
Big Lime			1342	1402			
Big Injun			1402	1505			
Fifty Feet			1894				
Thirty Feet			1970	2030			
Gordon Stray			2075				
Gordon			2195	2210			
Fourth			2220	2264			
Fifth			2363	2368			
Sand			2720	2745			
Speechley			3037	3047			
Gas			3038				
Gas			3044				
Total Depth			3057				
							Gas 1902 to 1960
							Oil 2227 - Gas 2225 Top Second Fourth Top 2272 Bot. 2288



FEB 11 1952 (Over)