

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator their respective addresses.

Farm name: Buffington, Doris Operator Well No.: Buffington #1  
 LOCATION: Elevation: 682 Quadrangle: Bellevue  
 District: Grant County: Jackson  
 Latitude: 4318509.102 Feet South of \_\_\_\_\_ Deg. \_\_\_\_\_ Min. \_\_\_\_\_ Sec.  
 Longitude: 437883.014 Feet West of \_\_\_\_\_ Deg. \_\_\_\_\_ Min. \_\_\_\_\_ Sec.

RECEIVED  
Office of Oil and Gas  
MAR 24 2016  
WV Department of  
Environmental Protection

Well Type: OIL \_\_\_\_\_ GAS X

Company Durst Oil and Gas, Inc. Coal Operator \_\_\_\_\_ N/A  
505 Cherry Lane or Owner \_\_\_\_\_  
Point Pleasant, WV 25550  
 Agent Ronald W. Durst, Jr. Coal Operator \_\_\_\_\_ N/A  
 Permit Issued Date 03-10-2016 or Owner \_\_\_\_\_

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Jackson ss:

Justin Meadows and Chad Harper being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 16th day of MARCH, 2016, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Cement	2080'	1930'	2 3/8" 2085'	0
Cement	1500'	1350'	4 1/2" 421'	1724'
Cement	682'	530'	8 5/8" 0'	100'
Cement	471'	371'	Cut 4 1/2 at 1425'; 678'; 421'; free	
Cement	150'	surface	Tried to back 8 5/8" off	
6 % gel between all plugs				

Description of monument: 7" x 6' Long with API # Welded on it and that the work of plugging and filling said well was completed on the 18th day of March, 2016.

And further deponents saith not. Justin Meadows  
CHAD HARPER



Sworn and subscribe before me this 22<sup>nd</sup> day of March, 2016

My commission expires: June 3, 2020  
Mildred L. Casto  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: [Signature] Title: odg Inspector **03/25/2016**