

Office of Oil and Gas
1356 Hansford Street
Charleston, WV 25301
Phone: (304) 558-6075
Fax: (304) 558-6047

West Virginia Department of Environmental Protection

Bob Wise,
Governor

Stephanie R. Timmermeyer,
Cabinet Secretary

September 22, 2004

FINAL INSPECTION REPORT

WELL PLUGGING PERMIT RELEASED

SMITH, CARL E PETROLEUM INC,

The FINAL INSPECTION REPORT for the permit, API Well Number: 47-3502405, issued to SMITH, CARL E PETROLEUM INC, and listed below has been received in this office. Your Affidavit of Plugging was received and reclamation requirements approved. The well designated by the permit number below has been released under your bond.



JAMES MARTIN
Chief,
Office of Oil and Gas

Operator: SMITH, CARL E PETROLEUM INC
Operator's Well No: 336
Farm Name: HARBIN, GERTRUDE
API Well Number: 47-3502405
Date Issued: 09/23/1999

STATE OF WEST VIRGINIA
DIVISION OF ENVIRONMENTAL PROTECTION
SECTION OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: HARBIN, GERTRUDE Operator Well No.: 336

LOCATION: Elevation: 618:00 Quadrangle: LIVERPOOL
District: GRANT County: JACKSON
Latitude: 12,600 Feet South of 39' Deg. Min. Sec.
Longitude 11,100 Feet West of 81 Deg. 35 Min. Sec.

Well Type: OIL _____ GAS X


Company: CARL E. SMITH PETROLEUM, INC.
P. O. BOX 4
SANDYVILLE, WV 25275-0004

Coal Operator
or Owner _____

Agent: LARRY D. SMITH

Coal Operator
or Owner _____

Permit Issued: 02-09-98



AFFIDAVIT

STATE OF WEST VIRGINIA,
County of JACKSON ss:

BILL WEEKLY and JOHN BOYD, SR. being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and HOMER DOUGHERTY Oil and Gas Inspector representing the Director, say that said work was commenced on the 12th day of AUGUST, 1999, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	Bottom LEFT
CEMENT	4,970 TD	4,596'	NONE	4-1/2" at 4,921'
GEL	4,596'	2,605'		
CEMENT	2,605'	2,385'		
GEL	2,385'	2,078'	2,641' 4-1/2"	2,280" 4-1/2"
CEMENT	2,078'	1,978'		
GEL	1,978'	653'		
CEMENT	653'	543'	647' 7"	1,356' 7"
GEL	543'	75'		
CEMENT	75'	0'		

Description of monument: 7" CASING WITH API NO. AT TOP OF WELL
and that the work of plugging and filling said well was completed on the 17th day of AUGUST, 1999.

And further deponents saith not.

Sworn and subscribe before me this 10th day of September, 1999
My commission expires: 9/27/99

Bill Weekly
John L. Boyd Sr.
Dean Ann Cox
Notary Public
H. H. Dougherty
Oil and Gas Inspector:

