

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: ADKINS, SINDA M. Operator Well No.: PERKINS 358

LOCATION: Elevation: 943' Quadrangle: KENTUCK
District: WASHINGTON County: JACKSON

Latitude: 38.722041602143 Feet South of _____ Deg. _____ Min. _____ Sec.

Longitude: -81.5652141143793 Feet West of _____ Deg. _____ Min. _____ Sec.

Well Type: OIL _____ GAS X

Company ALLIANCE PETROLEUM CO., LLC Coal Operator NO DECLARATION
101 MCQUISTON DRIVE or Owner _____
JACKSON CENTER, PA 16133 _____

Agent JEFF MAST Coal Operator NO DECLARATION
Permit Issued Date 3/29/2021 or Owner _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of JACKSON ss:


MELVIN MYERS and JAMES PURSLEY being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 29TH day of APRIL, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
C1A CEMENT	1732'	1622'	1730' X 2.375" TBG	0
C1A CEMENT	1520'	1244'		
C1A CEMENT	949'	849'		738' X 9.625" CSG CTS
C1A CEMENT	580'	450'		
C1A CEMENT	100'	SURFACE		1691' X 7" CSG CTS

Description of monument: 7' CSG WITH API # 36" ABOVE GROUND and that the work of plugging and filling said well was completed on the 30TH day of APRIL, 2021.

And further deponents saith not. [Signatures]

Sworn and subscribe before me this 10th day of May, 2021



My commission expires: Sept. 18, 2022
Sandra L. Messer
Notary Public

Affidavit reviewed by the Office of Oil and Gas: [Signature] Title: 5-14-21

06/25/2021

Farm Name: PERKINS 511185
Operator Well #: 1156778
API #: 47-035-02834

Type (Cement/Gel)	Sacks	From	To	Pipe Removed	Left	Fluid Hauled
C1A cement	32	1732'	1622'			
C1A cement	53	1520'	1244'			
C1A cement	20	949'	849'			
C1A cement	25	580'	450'			
C1A cement	20	100'	0'	1730' 2" Tubbing		

4-29-21: PJSA. MIRU. 0 PSI on tbg. 37 PSI on 2x7. BWD. TOOHD LD and inspect 1732' of 2 3/8" tbg. TIH to 1732'. Pump 10 bbls 6% gel. Pump 32 sk C1A cement plug. TOOHD LD 40 joints tbg. WOC. Secure WH. SDFN.

4-30-21: PJSA. Ran tubing in and tagged bottom plug. Pumped 6% gel from 1622' to 1520'. Set plug from 1520' to 1244' with 53 sacks of C1A cement. Pumped 6% gel from 1244' to 949'. Set plug from 949' to 849' with 20 sacks of C1A cement. Pumped 6% gel from 849' to 580'. Set plug from 580' to 450' with 25 sacks of C1A cement. Pumped 6% gel from 450' to 100'. Set plug from 100' to 0' with 20 sacks of C1A cement. Rigged down and set monument.