

*Original*

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS



ORIGINAL

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Jones, H.C., etal Operator Well No.: A-10

LOCATION: Elevation: 656' Quadrangle: Romance  
District: Poca County: Kanawha  
Latitude: 4269123.30 gps Feet South of \_\_\_\_\_ Deg. \_\_\_\_\_ Min. \_\_\_\_\_ Sec.  
Longitude: 450824.00 gps Feet West of \_\_\_\_\_ Deg. \_\_\_\_\_ Min. \_\_\_\_\_ Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company Pillar Energy LLC. Coal Operator N/A  
1244 Martins Branch Rd or Owner \_\_\_\_\_  
Charleston, WV 25312  
Agent Jeff Isner Coal Operator N/A  
Permit Issued Date 6/14/2021 or Owner \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Roane ss:


Gary Rexroad and Darrell Shamblin being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 2nd day of August, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
cement	1589'	1395'	1560' 23/8" tubing	828' of 7" casing
gel	1395'	1220'	659' of 7" casing	30' of 103/4" casing
cement	1220'	1000'		left 103/4 to avoid disturbing stream bank
gel	1000'	723'		
cement	723'	615'		ripped holes in 7" at 1209,1179
gel	615'	400'	gel 295' to 157'	1147,1117,1081,1058,1029'
cement	400'	295'	cement 157' to surface	

Description of monument: 7" OD X 40" above ground level and that the work of plugging and filling said well was completed on the 10th day of August, 2021.

And further deponents saith not. Gary Rexroad  
Darrell Shamblin

Sworn and subscribe before me this 12 day of August, 2021



My commission expires: March 6, 2025  
Jacqueline T. Hays  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Jerry W. Hula 8-23-21 Title: Inspector Oil & Gas

08/27/2021