



STATE OF WEST VIRGINIA  
DEPARTMENT OF MINES  
OIL AND GAS WELLS DIVISION

Rotary   
Spudder   
Cable Tools   
Storage

Quadrangle Clendenin 1-4

WELL RECORD

Oil or Gas Well: OIL  
(KIND)

Permit No. KAN-2419

Company	Mareve Oil Corp.	Casing and Tubing	Used in Drilling	Left in Well	Packers
Address	P.O. Box 1228, Parkersburg, W. Va.	Size			Kind of Packer
Farm	L. C. Wilson Acres 279-3/4	16			Size of
Location (waters)	Wills Creek	13			Depth set
Well No.	4 Elev. 1039	10	8-5/8	255	255
District	BIG SANDY County Kanawha	6 5/8	Cement	Circ.	
The surface of tract is owned in fee by P. Jennings		5 3/16			Perf. top
Address Frame, W. Va.		4 1/2			Perf. bottom
Mineral rights are owned by L. C. Wilson		3			Perf. top
Address Charleston, W. Va.		2			Perf. bottom
Drilling commenced	8-10-69	Liners Used			
Drilling completed	9-13-69				
Date Shot	From To				

Attach copy of cementing record.

CASING CEMENTED 4 1/2 SIZE 2169 No. Ft 9-14-69 Date

Amount of cement used (bags) 150

Name of Service Co. HOWCO

COAL WAS ENCOUNTERED AT FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

WELL FRACTURED (DETAILS) 40,000 #20/40 & 1,500 #10/20 Sd & 41,500 gallons gelled fresh water


RESULT AFTER TREATMENT (Initial open flow or bbls.) 29 BOPD

ROCK PRESSURE AFTER TREATMENT HOURS

Fresh Water Feet Salt Water Feet

Producing Sand Big Injun Depth 2017-2055

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
Rock & Shale			0	200			
Shaly Sand			200	210			
Red Bed			210	250			
Rock, Sand, Shale			250	480			
Sandy Shale			480	1360			
Salt Sand			1360	1817			
Little Lime			1817	1856			
Pencil Cave			1856	1869			
Big Lime			1869	2017			
Big Injun			2017	2055			
Shale			2055	2165	(T.D.)		



(over)