

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE ST. MONONGAH WV 26554
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE ST. MONONGAH WV 26554
Address
M.H. PRITCHARD HEIRS (c/o PHILLIP PRITCHARD)
Lease or Property Owner
PO BOX 108 MANNINGTON, WV 26682
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE ST. MONONGAH, WV 26554
Complete Address
MANNINGTON 7.5'
Well Location
MANNINGTON
District
MARION
County
3352
Well No.
PRITCHARD, MILDRED H. HEIRS
Farm

STATE INSPECTOR SUPERVISING PLUGGING *Bill Humboldt* 3-4-14

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA, ss:

DELBERT MOORE and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 11th day of December, 2013 and that the well was plugged in the following manner:

Formation	Filling Material	Casing Size & Kind	Casing Pulled	Casing Left In
Cleaned 6 1/2" hole through 7" casing from the surface to the bottom of the 7" casing at 1805'. Continued to clean 6 1/2" hole from 1805' to 2154'. Tagged solid plug at 2154'. Removed 1112' of 7" casing from the hole from the surface to 1112'. Cleaned 9 7/8" hole through 10 3/4" casing from the surface to the bottom of the 10 3/4" casing at 256'. Continued to clean 9 7/8" hole from 256' to 1112'. Tagged top of 7" casing at 1112'. Cut remaining 7" casing at the following depths: 1705', 1605', 1505', 1405', 1318' and 1212'. Cleaned 9 7/8" hole through the Pittsburgh Coal seam from 549' to 555'.		16" Conductor	0'	20'
		10 3/4" Casing	0'	256'
		7" Casing	1112'	693'
<u>Cemented hole from 2154' back to surface as follows:</u> From 2154' to 755' with 290 sacks of 35/65 Poz Cement. From 755' to 449' with 145 sacks of Thixotropic Cement with green dye. From 449' to the surface with 115 sacks of Econofill Cement. Cement did circulate at the surface. A total of 550 sacks of cement was used to cement the hole from 2154' to the surface. Cement did circulate at the surface. Left 20' of 16" conductor casing in the well from the surface to 20'.				
<u>Coal Seams</u>		<u>Description of Monument</u>		
<u>PITTSBURGH</u>	549' to 555'	77" of 7" casing w/company name, well number, permit number and date cemented stated on 7"		
(Name)		casing. Well marker will be attached to the		
(Name)		cement plug at ground level.		

RECEIVED
Office of Oil & Gas
MAR 13 2014

WV Department of
Environmental Protection

... And that the work of plugging and filling said well was completed on the 6th day of January, 2014

And further deponents saith not.

Delbert Moore
Delbert Moore


Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 27th day of January 2014

Kara Beth Frost
Notary Public

My commission expires: 11/4/23

Permit No. 47-49-00803-P
Well No. 3352



03/14/2014