

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE ST. MONONGAH WV 26582
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE ST. MONONGAH WV 26582
Address
CONSOLIDATION COAL CO.
Lease or Property Owner
1 BRIDGE ST. MONONGAH WV 26582
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE ST. MONONGAH, WV 26582
Complete Address
GLOVER GAP
Well Location
MANNINGTON
District
MARION
County
3973
Well No.
CONSOLIDATION COAL CO.
Farm

STATE INSPECTOR SUPERVISING PLUGGING Sam O'Wan III 3/14/12

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

DELBERT MOORE and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 3rd day of March, 2011 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Plugs Used Size & Kind	Casing Pulled	Casing Left In
	Cleaned 12 1/4" hole from the surface to 236'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 236' to 1104'. Top of 8 5/8" casing at 1104'. Drilled cement from 983' to 1048'. Reduced hole to 7 7/8". Cleaned 7 7/8" hole from 1104' to 1584'. Tagged plug at 1584'. Removed 8 5/8" casing from 1104' to 1211'. Left 367' of 8 5/8" casing in the hole from 1211' to 1578'. Cut remaining 8 5/8" casing at 1486' and 1386'. Cleaned 9 7/8" hole thru the Pittsburgh Coal 1055' to 1062'. Left 20' of 16" conductor pipe in the hole from 20' to surface.	16" Conductor 8 5/8" Casing	0' 107'	14' 367'
Coal Seams		Description of Monument		
<u>PITTSBURGH</u>	<u>1055' to 1062'</u>	77" of 7" casing w/company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to the cement plug at ground level.		
(Name)				
(Name)				
(Name)				

... and that the work of plugging and filling said well was completed on the 22nd day of March, 2011



And further deponents saith not.

Delbert E Moore
Delbert Moore

Kevin S. Wright
Kevin S. Wright

Jacqueline L Shriver
Notary Public

Permit No. 47-49-02147-P REVISED
Well No. 3973



My commission expires:

March 18, 2020