

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE ST. MONONGAH WV 26582
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE ST. MONONGAH WV 26582
Address
LARRY F. ORLOFF
Lease or Property Owner
1109 EVERGREEN DR. MANNINGTON, WV 26582
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE ST. MONONGAH, WV 26582
Complete Address
GLOVER GAP 7.5'
Well Location
MANNINGTON
District
MARION
County
5167
Well No.
ORLOFF, LARRY F.
Farm

RECEIVED
Office of Oil & Gas
DEC 21 2011

STATE INSPECTOR SUPERVISING PLUGGING *Bill Handuska*

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

WV Department of
Environmental Protection

RUSSELL SMALLWOOD and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 18th day of October, 2011 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Plugs Used Size & Kind	Casing Pulled	Casing Left In
	Cleaned 12 1/4" hole from the surface to 272'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 272' to the top of the 7" casing at 758'. Reduced hole to 6 1/4". Cleaned 6 1/4" hole from 758' to 2285'. Tagged plug at 2285'. Removed 728' of 7" casing from 758' to 1486'. Left 627' of 7" casing in the hole from 1486' to 2113'. Cut remaining 7" casing at the following depths; 2034', 1939', 1834', 1797', 1694' and 1592'. Cleaned 7 7/8" hole from 758' to the top of the remaining 7" casing at 1486'. Cleaned 7 7/8" hole through the Pittsburgh Coal 846' - 854'. Left 16' of 16" conductor pipe in the hole from 16' to surface.	16" Conductor 7" Casing	0' 728'	16' 627'
Cemented hole from 2285' back to surface as follows: From 2285' to 1061' with 236 sacks of Expandable Cement. From 1061' to 746' with 120 sacks of Thixotropic Cement with green dye. From 746' to surface with 218 sacks of Expandable Cement. A total of 574 sacks of cement were used to fill the hole from 2285 to surface. Cement did circulate at the surface.				
Coal Seams		Description of Monument		
<u>PITTSBURGH</u>	846' to 854'	77" of 7" casing w/company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to the cement plug at ground level.		
(Name)				
(Name)				
(Name)				

... and that the work of plugging and filling said well was completed on the 3rd day of November, 2011


And further deponents saith not.

Russell Smallwood
Russell Smallwood

Kevin S. Wright
Kevin S. Wright

Jacqueline L. Shriver
Notary Public

Permit No. 47-49-02188-P
Well No. 5167



Sworn to and subscribed before me this 15th day of December, 2011

My commission expires:

March 18, 2020

