

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE ST. MONONGAH WV 26554
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE ST. MONONGAH WV 26554
Address
SHERMAN W. HAYS
Lease or Property Owner
539 REX RUN RD. MANNINGTON, WV 26582
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE ST. MONONGAH, WV 26554
Complete Address
GLOVER GAP 7.5'
Well Location
MANNINGTON
District
MARION
County
5070
Well No.
HAYS, SHERMAN W.
Farm

STATE INSPECTOR SUPERVISING PLUGGING *William Handus* 2-17-12

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MIKE MITCHELL and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 22nd day of December, 2011 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Plugs Used Size & Kind	Casing Pulled	Casing Left In
	Cleaned 12 1/4" hole from the surface to 44'. Reduce hole to 9 7/8". Cleaned 9 7/8" hole from 44' to 1246'. Tagged plug at 1246'. Cleaned 9 7/8" hole through the Pittsburgh Coal 884' to 890'. Left 9' of 16" conductor pipe in the hole from 9' to surface.	16" Conductor	0'	9'
	<u>Cemented hole from 1246' back to surface as follows:</u> From 1246' to 1090' with 120 sacks of 35/65 Poz Mix Cement. From 1090' to 784' with 160 sacks of Thixotropic Cement with green dye. From 784' to surface with 242 sacks of Econofill Cement. A total of 522 sacks of cement were used to fill the hole from 1246' to surface. Cement did circulate at the surface.			
<u>Coal Seams</u>		<u>Description of Monument</u>		
<u>PITTSBURGH</u>	884' to 890'	77" of 7" casing w/company name, well number,		
(Name)		permit number and date cemented stated on 7"		
(Name)		casing. Well marker will be attached to the		
(Name)		cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 9th day of January, 2012

And further deponents saith not.

Mike Mitchell
Mike Mitchell


Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 16th day of February, 2012

Jacqueline L. Shriver
Notary Public

My commission expires:

March 18, 2020



Permit No. 47-49-02196-P
Well No. 5070