

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE ST. MONONGAH WV 26554  
Address  
CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE ST. MONONGAH WV 26554  
Address  
MARTHA A CYPHERS  
Lease or Property Owner  
1439 DENTS RUN ROAD MANNINGTON, WV 26582  
Address

CONSOLIDATION COAL CO.  
Name of Well Operator  
1 BRIDGE ST. MONONGAH, WV 26554  
Complete Address  
CLOVER GAP 7.5'  
Well Location  
MANNINGTON  
District  
MARION  
County  
5160  
Well No.  
CYPHERS, MARTHA A  
Farm

STATE INSPECTOR SUPERVISING PLUGGING William H. Hensley 5-30-13

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

MIKE MITCHELL and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 4<sup>th</sup> day of April, 2013 and that the well was plugged in the following manner:

Formation	Filling Material	Casing Size & Kind	Casing Pulled	Casing Left In
Cleaned 12 1/2" hole from the surface to 268'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 268' to 1110'. Tag top of 7" casing at 1110'. Reduced hole to 6 1/2". Cleaned 6 1/2" hole inside 7" casing from 1110' to 1891'. Cut 7" casing at the following depths: 1885', 1785', 1680', 1584', 1484, 1384', 1284' and 1198'. Left unknown amount of 7" casing in the hole from 1110' to unknown depth. Cleaned 9 7/8" hole through the Pittsburgh coal seam from 896' to 901'. Left 16' of 16" conductor casing in the hole from the surface to 16'.		16" Conductor	0'	16'
		7" Casing	0'	Unknown
<b>RECEIVED</b> Office of Oil & Gas MAY 30 2013 WV Department of Environmental Protection				
<b>Cemented hole from 1891' back to surface as follows:</b> From 1891' to 1101' with 105 sacks of 35/65 Poz Mix Cement. From 1101' to 786' with 140 sacks of Thixotropic Cement w/ dye. From 786' to surface with 300 sacks of Econofill Cement. A total of 545 sacks of cement was used to cement the hole from 1891' to surface. Cement did circulate at the surface.				
<u>Coal Seams</u>		<u>Description of Monument</u>		
<u>PITTSBURGH</u>	896' to 901'	77" of 7" casing w/company name, well number,		
(Name)		permit number and date cemented stated on 7"		
(Name)		casing. Well marker will be attached to the		
(Name)		cement plug at ground level.		

... And that the work of plugging and filling said well was completed on the 22<sup>nd</sup> day of April, 2013

And further deponents saith not.

Mike Mitchell  
Mike Mitchell


Kevin S. Wright  
Kevin S. Wright

Sworn to and subscribed before me this 21<sup>st</sup> day of May 2013

Carole A Mayle  
Notary Public

My commission expires: 9-12-17

Permit No. 47-49-02252-P  
Well No. 5160



05/31/2013