

ORIGINAL

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE ST. MONONGAH WV 26554
Address

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE ST. MONONGAH WV 26554
Address

CONSOLIDATION COAL COMPANY
Lease or Property Owner
1 BRIDGE ST MONONGAH, WV 26554
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE ST. MONONGAH, WV 26554

Complete Address
CLOVER GAP 7.5'
Well Location
MANNINGTON

District
MARION
County
5049

Well No.
CONSOLIDATION COAL COMPANY
Farm

STATE INSPECTOR SUPERVISING PLUGGING

[Signature]

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MIKE MITCHELL and **KEVIN S. WRIGHT** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 9th day of July, 2013 and that the well was plugged in the following manner:

Formation	Filling Material	Casing Size & Kind	Casing Pulled	Casing Left In
Cleaned 12 1/4" hole from the surface to 306'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 306' to 1228'. Reduced hole to 7 7/8". Cleaned 7 7/8" hole from 1228' to 1707' Reduced hole to 6 1/2". Tagged solid plug at 1707'. Cleaned 9 7/8" hole through the Pittsburgh Coal seam from 801' to 809'.		16" Conductor	0'	12'
<p>Cemented hole from 1707' back to surface as follows: From 1707' to 1009' with 235 sacks of 35/85 Poz Cement. From 1009' to 701' with 160 sacks of Thixotropic Cement w/ dye. From 701' to surface with 255 sacks of Econofill Cement. A total of 650 sacks of cement was used to cement the hole from 1707' to the surface. Cement did circulate at the surface. Left 12' of 16" conductor casing in the hole from the surface to 12'.</p>				
Coal Seams		Description of Monument		
<u>PITTSBURGH</u>	801' to 809'	77" of 7" casing w/company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to the cement plug at ground level.		
(Name)				
(Name)				
(Name)				

RECEIVED
Office of Oil & Gas
SEP 11 2013
WV Department of
Environmental Protection

... And that the work of plugging and filling said well was completed on the 23rd day of July, 2013

And further deponents saith not.

[Signature]
Mike Mitchell


[Signature]
Kevin S. Wright

Sworn to and subscribed before me this 19 day of August

[Signature]
Notary Public

My commission expires: Feb. 16, 2021

Permit No. 47-49-02267-P
Well No. 5049



09/27/2013