

AFFIDAVIT OF PLUGGING AND FILLING WELL

ORIGINAL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE ST. MONONGAH WV 26554
Address

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE ST. MONONGAH WV 26554
Address
MARK A. AND CARRIE A HENDERSHOT
Lease or Property Owner
714 DELAWARE AVE. FAIRMONT, WV 26554
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE ST. MONONGAH, WV 26554
Complete Address
CLOVER GAP 7.5'
Well Location
MANNINGTON
District
MARION
County
5067
Well No.
HENDERSHOT, MARK A & CARRIE
Farm

STATE INSPECTOR SUPERVISING PLUGGING Bill Hendershot 9-6-13
AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MIKE MITCHELL and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 25th day of July, 2013 and that the well was plugged in the following manner:

| Formation | Filling Material | Casing Size & Kind | Casing Pulled | Casing Left In |
|--|------------------|---|---------------|----------------|
| Cleaned 12 1/2" hole from the surface to 326'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 326' to 1248'. Reduced hole to 7 7/8". Cleaned 7 7/8" hole from 1248' to 1377'. Reduced hole to 6 1/2". Cleaned 6 1/2" hole from 1377' to 1427'. Cleaned 9 7/8" hole through the Pittsburgh Coal seam from 1011' to 1018'. <u>Cemented hole from 1427' back to surface as follows:</u> From 1427' to 1218' with 110 sacks of 35/65 Poz Cement. From 1218' to 911' with 170 sacks of Thixotropic Cement w/ dye. From 911' to surface with 385 sacks of Econofill Cement. A total of 665 sacks of cement was used to cement the hole from 1427' to the surface. Cement did circulate at the surface. Left 10' of 16" conductor casing in the hole from the surface to 10'. | 16" Conductor | 0' | 10' | |
| <u>Coal Seams</u> | | <u>Description of Monument</u> | | |
| <u>PITTSBURGH</u> | 1011' to 1018' | 77" of 7" casing w/company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to the cement plug at ground level. | | |
| (Name) | | | | |
| (Name) | | | | |
| (Name) | | | | |

RECEIVED
Office of Oil & Gas
SEP 11 2013
WV Department of
Environmental Protection

... And that the work of plugging and filling said well was completed on the 12th day of August, 2013

And further deponents saith not.

Mike Mitchell
Mike Mitchell


Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 3rd day of September

Monica DeFelice
Notary Public

My commission expires: February 16, 2021

Permit No. 47-49-02268-P
Well No. 5067



09/27/2013