

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Robert Jones Operator Well No.: Jones 3H

LOCATION: Elevation: 1133.0' Quadrangle: Glover Gap WW

District: Mannington County: Marion

Latitude _____ Feet South of 39 Deg. 58 Min. 57.41 Sec.

Longitude: _____ Feet West of -80 Deg. 42 Min. 71.56 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554

Agent David Roddy Coal Operator _____
or Owner _____

Permit Issued Date 10/30/2023 _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Marion ss:

Matthew A. Yearsley and Delbert Moore being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 17th day of December, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED		LEFT
Expanding Cement w/ Gas Blocker	7,113'	1530'	5 1/2"	0'	13,115' - Multiple cuts and perforations
Thixotropic Cement w/ Green Dye	1530'	536'	9 5/8"	0'	3,039' - Multiple Perforations
Expanding Cement w/ Gas Blocker	536'	Surface	13 3/8"	0'	1,015' - Multiple Perforations
			20"	0'	118'

Description of monument: 96' of 7" casing with company name, well#, API# and date cemented and that the work of plugging and filling said well was completed on the 17th day of December, 2023.

And further deponents saith not. Delbert L. Moore
Matthew A. Yearsley



Sworn and subscribe before me this 25th day of January, 2024

My commission expires: June 8, 2027
Christopher Willis
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Ky Willott Title: Inspector

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATED, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address

WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

Well Location
MANNINGTON
District
MARION
County
JONES 3H
Well No.
ROBERT JONES
Farm

JASON G. & MICHELLE R. STOUT
Lease or Property Owner
637 UPPER MURRAY RD, MANNINGTON, WV 26582
Address

STATE INSPECTOR SUPERVISING PLUGGING

Ky Willett

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MARION ss:

MATTHEW A. YEARSLEY and DELBERT MOORE being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 3rd day of December, 2023 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
The well was killed with 318 bbls of 10F Brine. Wireline set as CIBP at 7,136'. Plug was tested for one hour at 80% of the 10,000 lb. rating. After a successful test, a second CIBP was set at 7,126' and tested for one hour at 80% of the 10,000 lb. rating. Cleaned through 5 1/2" casing from surface to 7114' tagging CIBP. Cemented from 7114' up to 5505' with 140 sacks of expanding cement with a Gas Blocker additive. Wireline cut 5 1/2" casing 5480' and attempted to remove 5 1/2" casing by pulling 150% over string with no success. Perforated 5 1/2" casing at the following depths with six shots per depth (5380', 5280', 5180', 5080', 4980', 4880', 4780', 4680', 4580', 4480', 4380', 4280', 4180', 4080', 3980', 3880', 3780', 3680', 3580', 3480', 3380'). Cemented from 5505' up to 3296' with 195 sacks of Expanding Cement with a Gas Blocker additive. Cut 5 1/2" casing at 3301' and attempted to remove 5 1/2" casing by pulling 150% over string with no success. Perforated 5 1/2" casing at the following depths with six shots per depth (3280', 3180', 3080', 2980', 2880', 2780', 2680', 2580', 2480', 2380', 2280', 2180', 2080', 1980', 1880', 1780', 1680', 1580'). Cemented from 3296' up to 1530' with 180 sacks of Expanding Cement with a Gas Blocker additive. Wireline cut 5 1/2" casing at 1530' and 1470' and attempted to remove 5 1/2" casing by pulling 150% over string with no success. Perforated 5 1/2" casing at following depth with six shot per depth (1342', 1292', 1242', 1192', 1142', 1092', 1042', 992'). Cut 5 1/2" casing at 418' and 200', attempted to remove 5 1/2" casing by pulling 150% over string with no success. Perforated 5 1/2", 9 5/8" and 13 3/8" casing through Pittsburgh Coal seam from 936 to 942 at following depths with six shots per depth (952', 947', 942', 940', 936', 936', 931', 926', 888', 836'). The casing depths were taken from the original well record.				
Cemented the hole from 1530' to surface as follows:				
Cemented from 1530' up to 536' with 110 sacks of Thixotropic Cement with green dye and Gas Blocker additive. Cemented from 536 to surface with 65 sacks of Expanding Cement with Gas Blocker additive. Cement circulated at the surface.				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>936' - 942'</u>	<u>96" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.</u>		

... and that the work of plugging and filling said well was completed on the 17th day of December, 2023

And further deponents saith not.


Matthew A. Yearsley
Matthew A. Yearsley

Delbert L. Moore
Delbert Moore

Sworn to and subscribed before me this 25th day of January, 2024

Christopher Andrew Willis
Notary Public

My commission expires:
June 8, 2027



Permit No. 47-049-02283-00-00
Well No. Jones 3H
Latitude: 39° 58' 57.41" N
Longitude: -80° 42' 71.56" W