

Original

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE ST. MONONGAH WV 26554  
Address  
CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE ST. MONONGAH WV 26554  
Address  
CONSOLIDATION COAL CO.  
Lease or Property Owner  
1 BRIDGE ST. MONONGAH, WV 26554  
Address

CONSOLIDATION COAL CO.  
Name of Well Operator  
1 BRIDGE ST. MONONGAH, WV 26554  
Complete Address  
GLOVER GAP 7.5'  
Well Location  
MANNINGTON  
District  
MARION  
County  
5058  
Well No.  
CONSOLIDATION COAL COMPANY  
Farm

STATE INSPECTOR SUPERVISING PLUGGING *Bill Woodard* 3-12-14

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

RUSSELL SMALLWOOD and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 14<sup>th</sup> day of February, 2014 and that the well was plugged in the following manner:

Formation	Filling Material	Casing Size & Kind	Casing Pulled	Casing Left In
	Cleaned 12 1/2" hole from surface to 350'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 350' to 947'. Cleaned 9 7/8" hole through the Pittsburgh Coal seam from 696' to 702'. Possible small junk metal remains through the Pittsburgh Coal seam from 696' to 702'. Reduced hole to 7 7/8". Cleaned 7 7/8" hole from 947' to 1189'. Tagged solid plug at 1189'.  Cemented hole from 1189' back to surface as follows: From 1189' to 912' with 85 sacks of Expandable Cement. From 912' to 566' with 160 sacks of Thixotropic Cement with green dye. From 566' to surface with 295 sacks of Expandable Cement. Cement did circulate at the surface. Left 18' of 16" conductor casing in the hole from the surface to 18'.	16" Conductor	0'	18'
Coal Seams		Description of Monument		
<u>PITTSBURGH</u>	696' to 702'	2' X 2' flat plate with Consol Coal		
(Name)		API # 47-49-02285, Well #5058		
(Name)		and date plugged 2/25/2014 stated on flat plate		
(Name)				

RECEIVED  
Office of Oil & Gas  
MAR 24 2014  
WV Department of  
Environmental Protection

... And that the work of plugging and filling said well was completed on the 25<sup>th</sup> day of February, 2014.

And further deponents saith not.

*Russell Smallwood*  
Russell Smallwood


*Kevin S. Wright*  
Kevin S. Wright

Sworn to and subscribed before me this 10<sup>th</sup> day of March 2014

*Kara Beth Forst*  
Notary Public

My commission expires: November 4, 2023

Permit No. 47-49-02285-P  
Well No. 5058



03/28/2014