

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WILLIAM C. & VICKIE E. LUCAS
Lease or Property Owner
85 EVANS RUN RD MANNINGTON, WV 26582
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
GLOVER GAP 7.5'
Well Location
MANNINGTON
District
MARION
County
5355
Well No.
LUCAS, WILLIAM C. & VICKIE E.
Farm

STATE INSPECTOR SUPERVISING PLUGGING *[Signature]* 7-1-14

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MARK WILSON and **KEVIN WRIGHT** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 8th day of April, 2014 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned 12 1/4" hole from Surface to 217'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 217' to 1002'. Cleaned 9 7/8" hole through the Pittsburgh Coal seam from 896' to 905'. Reduced hole to 7 7/8". Cleaned 7 7/8" hole from 1002' to 1762'. Left 81' of 8 5/8" casing in the hole from 1306' to 1387'.		16" Conductor	0'	20'
		8 5/8" Casing	0'	81'
Cemented hole from 1762' back to surface as follows: From 1762' to 1105' with 260 sacks of Expandable Cement. From 1105' to 796' with 150 sacks of Thixotropic Cement with green dye. From 796' back to the Surface with 260 sacks of Expandable Cement. Cement did circulate at the surface. Left 20' of 16" conductor casing in the hole from the surface to 20'.				
Coal Seams	Description of Monument			
Pittsburgh	(896' - 905')	77' of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

Received
Office of Oil & Gas
AUG 26 2014

... and that the work of plugging and filling said well was completed on the 18th day of April, 2014


And further deponents saith not.

Mark Wilson
Mark Wilson
Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 30th day of June, 2014

[Signature]
Notary Public

My commission expires: 08/16/17



Permit No. 47-049-02294-P
Well No. 5355

08/29/2014