

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL CO.
Lease or Property Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
GLOVER GAP 7.5'
Well Location
MANNINGTON
District
MARION
County
5044
Well No.
CONSOLIDATION COAL COMPA
Farm

STATE INSPECTOR SUPERVISING PLUGGING *[Signature]* 10-2-14

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MICHAEL MITCHELL and **STEPHAN MOATS** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 28th day of August, 2014 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned 12 1/2" hole from Surface to 347'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 347' to 1198'. Reduced hole to 6 1/2". Cleaned 6 1/2" hole from 1198' to 1201'. Cleaned 9 7/8" hole through the Pittsburgh Coal seam from 851' to 858'.		16" Conductor	0'	15'
<p>Cemented hole from 1201' back to surface as follows: From 1201' to 1058' with 55 sacks of Expandable Cement. From 1058' to 751' with 155 sacks of Thixotropic Cement with dye. From 751' back to the Surface with 375 sacks of Expandable Cement. Cement did circulate at the Surface. Left 15' of 16" conductor casing in the hole from Surface to 15'.</p>				
Coal Seams		Description of Monument		
Pittsburgh	(851' - 858')	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

Received
Office of Oil & Gas
OCT 02 2014

... and that the work of plugging and filling said well was completed on the 9th day of September, 2014

And further deponents saith not.


[Signature]
Michael Mitchell

[Signature]
Stephan Moats

Sworn to and subscribed before me this 29 day of September 2014

[Signature]
Notary Public

My commission expires: 11/4/23



Permit No. 47-049-02326-P
Well No. 5044

10/10/2014