

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATED, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
MICHAEL, JEFFREY H. & RONALD C.  
Lease or Property Owner  
PO BOX 221 MANNINGTON, WV 26582  
Address

CONSOLIDATION COAL CO.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
GLOVER GAP 7.5'  
Well Location  
MANNINGTON  
District  
MARION  
County  
5246  
Well No.  
MICHAEL, JEFFREY H. & RONALD C.  
Farm

STATE INSPECTOR SUPERVISING PLUGGING *William H. ...*

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

RUSSELL SMALLWOOD and KEVIN WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 15<sup>th</sup> day of September, 2014 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cleansed 12 1/2" hole from Surface to 254'. Reduced hole to 9 7/8". Cleansed 9 7/8" hole from 254' to 1408'. Cleansed 9 7/8" hole through the Pittsburgh Coal seam from 938' to 945'. Reduced hole to 7 7/8". Cleansed 7 7/8" hole from 1408' to 1797'. Reduced hole to 6 1/2". Cleansed 6 1/2" hole from 1797' to 1864'. Tagged solid plug at 1864'.		16" Conductor	0'	15'
<u>Cemented hole from 1864' back to surface as follows:</u> From 1864' to 1145' with 155 sacks of Expandable Cement. From 1145' to 838' with 195 sacks of Thixotropic Cement with green dye. From 838' back to the Surface with 380 sacks of Expandable Cement. Cement did circulate at the surface. Left 15' of 16" Conductor Casing in the hole from Surface to 15'.				
Coal Seams		Description of Monument		
Pittsburgh	(938' - 945')	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

RECEIVED  
Office of Oil and Gas  
NOV 17 2014  
WV Department of  
Environmental Protection

... and that the work of plugging and filling said well was completed on the 26<sup>th</sup> day of September, 2014

And further deponents saith not.


*Russell Smallwood*  
Russell Smallwood

*Kevin S. Wright*  
Kevin S. Wright

Sworn to and subscribed before me this 27 day of October, 2014

*Kara Balthasar*  
Notary Public

My commission expires: 11/4/13



Permit No. 47-049-02349-P  
Well No. 5246