

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
JEFFREY MICHAEL
Lease or Property Owner
PO BOX 221 MANNINGTON, WV 26582
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
GLOVER GAP 7.5'
Well Location
MANNINGTON
District
MARION
County
5142
Well No.
MICHAEL JEFFREY
Farm

STATE INSPECTOR SUPERVISING PLUGGING *[Signature]* 12-15-14

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

RUSSELL SMALLWOOD and KEVIN WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 28th day of September, 2014 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned 12 3/4" hole from Surface to 236'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 236' to 1000'. Cleaned 9 7/8" hole through the Pittsburgh Coal seam from 845' to 851'. Tagged top of 7" casing at 1000'. Reduced hole to 6 1/2". Cleaned 6 1/2" hole from 1000' to 1248'. Tagged solid plug at 1248'. Removed 102' of 7" casing from 1000' to 1102'. Left an unknown amount of 7" casing in the hole from 1102' to an unknown depth.		16" Conductor 7" Casing	0' 102'	16' Unknown
<u>Cemented hole from 1248' back to surface as follows:</u> From 1248' to 1051' with 35 sacks of Expandable Cement. From 1051' to 745' with 170 sacks of Thixotropic Cement with green dye. From 745' back to the Surface with 35 sacks of Expandable Cement. Cement did circulate at the surface. Left 16' of 16" Conductor Casing in the hole from Surface to 16'.				
Coal Seams		Description of Monument		
Pittsburgh	(845' - 851')	77' of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

RECEIVED
Office of Oil and Gas
DEC 17 2014
WV Department of
Environmental Protection

... and that the work of plugging and filling said well was completed on the 14th day of October, 2014


And further deponents saith not.

[Signature]
Russell Smallwood
[Signature]
Kevin S. Wright

Sworn to and subscribed before me this 1 day of December 2014

[Signature]
Kara Beth Forst
Notary Public

My commission expires: 11/4/23



Permit No. 47-049-02355-P
Well No. 5142

12/19/2014