

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

FREELAND W. MILLER  
Lease or Property Owner  
PO BOX 91 RACHEL, WV 26587  
Address

CONSOLIDATION COAL CO.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554

Complete Address  
MANNINGTON 7.5'  
Well Location  
MANNINGTON

District  
MARION

County  
3358

Well No.

MILLER, FREELAND W.  
Farm

STATE INSPECTOR SUPERVISING PLUGGING *[Signature]*

3-24-15

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

**ROGER MOORE and KEVIN S. WRIGHT** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 14<sup>th</sup> day of November, 2014 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Removed 790' of 8 5/8" casing from the hole from 8' to 798'. Left 472' of 8 5/8" casing in the hole from 798' to 1270'. Cut remaining 8 5/8" casing at the following depths: 808', 834' and 936'. Cleaned 9 7/8" hole from Surface to 798. Cleaned 9 7/8" hole through the Pittsburgh Coal seam from 721' to 728'. Reduced hole to 7 7/8". Cleaned 7 7/8" hole from 798' to 1850'. Left 20' of 16" conductor casing in the hole from Surface to 20'.		16" Conductor  8 5/8"	0'  790'	20'  472'
<p><b>Cemented hole from 1850' back to surface as follows:</b> From 1850' to 928' with 181 sacks of Expandable Cement. From 928' to 621' with 130 sacks of Thixotropic Cement with green dye. From 621' back to the Surface with 252 sacks of Expandable Cement. Cement did circulate at the Surface.</p>				
Coal Seams		Description of Monument		
Pittsburgh	(721' - 728')	77' of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

RECEIVED  
Office of Oil and Gas  
MAR 24 2015  
WV Department of  
Environmental Protection

... and that the work of plugging and filling said well was completed on the 15<sup>th</sup> day of December, 2014

And further deponents saith not.

*[Signature]*  
Roger Moore


*[Signature]*  
Kevin S. Wright

Sworn to and subscribed before me this 2 day of February 2015

*[Signature]*  
Notary Public

03/27/2015

My commission expires: 11/4/23



Permit No. 47-049-02373-P  
Well No. 3358