

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL COMPANY
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

CONSOLIDATION COAL COMPANY
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

JEFFREY H. MICHAEL
Lease or Property Owner
PO BOX 221, MANNINGTON, WV 26582
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address

GLOVER GAP 7.5'
Well Location
MANNINGTON

District
MARION
County

5251
Well No.

MICHAEL, JEFFREY H.
Farm

STATE INSPECTOR SUPERVISING PLUGGING Bob Heckel

3-24-15

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

DELBERT MOORE and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 15th day of December, 2014 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cleaned 12 1/2" hole from Surface to 229'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 229' to 977'. Reduced hole to 7 7/8". Cleaned 7 7/8" hole from 977' to 1087'. Reduced hole to 6 1/2". Cleaned 6 1/2" hole from 1087' to 1120'. Tagged solid plug at 1120'. Cleaned 9 7/8" hole through the Pittsburgh Coal seam from 731' to 737'. Left 20' of 16" conductor casing in the hole from Surface to 20'.		16"	0'	20'
<u>Cemented hole from 1120' back to the Surface as follows:</u> From 1120' to 937' with 70 sacks of Expandable Cement. From 937' to 631' with 170 sacks of Thixotropic Cement with green dye. From 631' back to the Surface with 320 sacks of Expandable Cement. Cement did circulate at the Surface.				
Coal Seams		Description of Monument	<p>RECEIVED Office of Oil and Gas MAR 24 2015 WV Department of Environmental Protection</p>	
<u>Pittsburgh</u>	<u>(731' - 737')</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 8th day of January, 2015.

And further deponents saith not.


Delbert Moore
Delbert Moore

Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 24th day of March 2015

03/27/2015

My commission expires: 9-12-17



Carole A. Mayle
Notary Public

Permit No. 47-049-02382-P
5251