

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

CONSOLIDATION COAL CO.  
Lessee or Property Owner  
1000 Consol Energy Drive Cannonsburg, PA 15317  
Address

CONSOLIDATION COAL CO.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address


MANNINGTON WV 7.5'  
Well Location  
MANNINGTON  
District

MARION  
County  
4033  
Well No.

JOS. M. ROWAND  
Farm



STATE INSPECTOR SUPERVISING PLUGGING



AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

ROGER D. MOORE and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 8<sup>th</sup> day of August, 2017 and that the well was plugged in the following manner:

| Sand or Zone Record   | Filling Material  | Casing/Tubing Size   | Casing Pulled | Casing Left In |
|---|-------------------|--|---------------|----------------|
| Formation   |                   |  |               |                |
| Cleaned 12 1/4" hole from the surface to 224'. Reduced hole to 9 7/8" bit. Cleaned hole with 9 7/8" bit from 224' to 1392'. Removed Junk Tubing from 1251' to 1360'. Reduced hole to 7 7/8" bit. Cleaned hole with 7 7/8" bit from 1392' to 1800'. Reduced hole to 6 1/2" bit. Cleaned hole with 6 1/2" bit from 1800' to T.D. 2074'.   |                   | 16" Conductor  | 0'            | 20'            |
| <b>Cemented hole from 2074' back to Surface as follows:</b><br>From 2074' to 1080' with 345 sacks of Expandable cement. From 1080' to 752' with 175 sacks of Thixotropic cement with green dye. From 752' to 312' with 140 sacks of Expandable cement. From 312' to surface with 160 sacks of Expandable cement. Finished top of well bore and rat hole with 15 sacks of Expandable cement. A total of 660 sacks of Expandable cement and 175 sacks of Thixotropic cement with green dye was used to cement in well. Left 20' of 16" Conductor in the well from the surface to 20'. |                   |  |               |                |
| Coal Seams  |                   | Description of Monument  |               |                |
| Pittsburgh  | (852.6' - 859.6') | 77' of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level. |               |                |

... and that the work of plugging and filling said well was completed on the 28<sup>th</sup> day of August, 2017

And further deponents saith not.

  
Roger D. Moore

  
Kevin S. Wright

Sworn to and subscribed before me this 11<sup>th</sup> day of Sept 2017

  
Carol A. Mays  
Notary Public

My commission expires: 8-12-17



Permit No. 47-049-02459-P  
Well No. 4033  
Latitude: 39° 33' 46.74"N  
Longitude: 80° 21' 55.88"W