

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: KRETZER Operator Well No.: 71395

LOCATION: Elevation: 1061' Quadrangle: MANNINGTON 7.5'
District: LINCOLN County: MARION
Latitude: 6299' Feet South of 39 Deg. 35 Min. 00 Sec.
Longitude: 10311' Feet West of 80 Deg. 15 Min. 00 Sec.

Well Type: OIL ☒ GAS ☒

Company UNKNOWN - WVDEPAID PLUGGING CONTRACT Coal Operator OHIO VALLEY RESOURCES INC, ET AL
601 57TH STREET or Owner 46226 NATIONAL ROAD
CHARLESTON, WV 25304 ST CLAIRSVILLE, OH 43950
Agent H. JASON HARMON Coal Operator _____
Permit Issued Date 04-30-2025 or Owner _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of LEWIS ss:

JAMES CLAYTON ("CLAY") COCHRAN and DAVID LEE BOWLES being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 22ND day of JULY, 2025, and the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
TAG TD	1850'		5/8" RODS (1820'); 2-3/8" TBG (1850')	NONE (5/8" RODS; 2-3/8" TBG)
BH PLUG CEMENT	1850'	1400'	PUMP CLASS A CEMENT (52 SACKS)	WATER SPACER (1400' - 1250')
CEMENT PLUG	1250'	1150'	PUMP CLASS A CEMENT (12 SACKS)	WATER SPACER (1150' - 1075')
PERF 8 HOLES	1069' & 300'	(4 SHOTS AT EACH INTERVAL)		
CEMENT PLUG	1075'	950'	PUMP CLASS A CEMENT (12 SACKS)	WATER SPACER (950' - 350')
SURFACE CEMENT PLUG	350'	SURFACE	PUMP CLASS A CEMENT (40 SACKS)	

Description of monument: ONE JOINT PIPE; 36" ABOVE; 10' BELOW; TO STATE SPECS and that the work of plugging and filling said well was completed on the 31ST day of JULY, 2025.

And further deponents saith not.

Sworn and subscribe before me this 6TH day of AUGUST, 2025

My commission expires: OCTOBER 10, 2029



Notary Public

Affidavit reviewed by the Office of Oil and Gas: Jeff A. Propp

Title: OOG Inspector 8-12-2025

08/15/2025



08/15/2025