

Company HOPE NATURAL GAS CO
 Address CLARKSBURG WVA
 Farm DEWEY BROCK

STATE OF WEST VIRGINIA
 DEPARTMENT OF MINES
 OIL AND GAS DIVISION
 CHARLESTON

LATITUDE 39 32 30

• -156
• 30W

LONGITUDE 80 12 30

7'5 OGIS topo location

7.5' loc _____ 15' loc _____
(calc.) _____

Company 9536 MP 110

Farm DEWEY BROCK

Quad GRANT TOWN

County MARION

District LINCOLN

WELL LOCATION MAP

File No. 30721

Lincoln District, Marion County, W. Va.
 By Hays Natural Gas Co., 445 E. Main St., Clarksburg, W. Va.
 Abandoned under permit No.-11
 On 25 acres.
 Elevation, 1085' L.
 Drilling commenced Nov. 19, 1923; completed Jan. 28, 1924.
 No water recorded.
 10" casing, 428'; 8", 1430'; 6", 1695'; 5", 2670'; all left in.
 Casing not cemented.
 Coal was encountered at 305-309 and 415-421'.
 Gas well. Record to Dept. of Mines dated May 21, 1951.
 Record to 309 from Mrs. Griffith Aug. 17, 1951. Old file No. 799.

	Top.	Bottom.
Mapleton (Sewickley) Coal	305	- 309
Pittsburgh Coal	415	- 421
Little Parkers Sand	785	- 805
Gas Sand	1170	- 1190
First Salt Sand	1230	- 1270
Second Salt Sand	1320	- 1445
Little lime	1645	- 1655
Pencil Gw	1655	- 1660
Big lime	1660	- 1730
Fifty-foot Sand	2240	- 2290
Thirty-foot Sand	2315	- 2390
Gordon Grey Sand	2628	- 2633
Gordon Sand	2643	- 2662
Fourth Sand	2666	- 2685
Fifth Sand (gas, 2775')	2773	- 2806
Total depth		2919



799

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

WELL RECORD

Permit No. MAR-721-A


Oil or Gas Well (KIND)

Company Hope Natural Gas Company.
 Address 445 West Main St. Clarksburg, W. Va.
 Farm Dewey Brock Acres 25
 Location (waters) _____
 Well No. 9536 M.P. 110 Elev. 1085
 District Lincoln County Marion.
 The surface of tract is owned in fee by _____
 Address _____
 Mineral rights are owned by _____
 Address _____
 Drilling commenced Nov. 19, 1923
 Drilling completed Jan. 28, 1924
 Date Shot _____ From _____ To _____
 With _____
 Open Flow _____ /10ths Water in _____ Inch
 _____ /10ths Merc. in _____ Inch
 Volume _____ Cu. Ft.
 Rock Pressure _____ lbs. _____ hrs.
 Oil _____ bbls., 1st 24 hrs.
 Fresh water none recorded feet _____ feet
 Salt water none recorded feet _____ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer
13			
10	<u>428</u>	<u>428</u>	Size of
8 3/4	<u>1430</u>	<u>1086</u>	
6 5/8	<u>1695</u>	<u>1695</u>	Depth set
5 3/16	<u>2670</u>	<u>2670</u>	
3			Perf. top
2			Perf. bottom
Liners Used			Perf. top
			Perf. bottom

NOT
 CASING CEMENTED _____ SIZE _____ No. Ft. _____ Date _____
 COAL WAS ENCOUNTERED AT 305 FEET 48 INCHES
415 FEET 72 INCHES FEET INCHES
 FEET INCHES FEET INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Mapletown Coal			305	309			
Pittsburgh Coal			415	421			
Little Dunkard			785	805			
Gas sand			1170	1190			
First Salt			1230	1270			
Second Salt			1320	1445			
Little Lime			1645	1655			
Pencil cave			1655	1660			
Big Lime			1660	1730			
Fifty foot			2240	2290			
Thirty foot			2315	2390			
Gordon stray			2628	2633			
Gordon			2643	2662			
Fourth			2666	2685			
Fifth			2773	2806	gas	2775	
Total dept.				2919			



AUG 17 1951

