




LATITUDE 39 37 30

LONGITUDE 80 07 30



2,185  
1,44W

7'5 OGIS topo location

7.5' loc \_\_\_\_\_ 15' loc \_\_\_\_\_  
 (calc.) \_\_\_\_\_

Company 9594 MP 256

Farm W H NEPTUNE

Quad GRANT TOWN

County MORISON

District POW POW

WELL LOCATION MAP

File No. 30730

W. H. MEPTUNE NO. 9594 (NO-256) WELL.

1307

Peapaw District, Marion County, W. Va.  
 By Hope Natural Gas Co., 445 W. Main St., Clarksburg, W. Va.  
 Abandoned under permit NAB-.....-A7

On 70 acres.

Elevation, 1045' L.

Drilling completed August 1, 1913.

Salt water at 1300'.

10" casing, 370' (pulled); 8 1/2", 1229' (pulled); 6 3/4", 1610'; 3" tubing, 1615'.

Casing not cemented.

Coal was encountered at 252-257 and 320-327'.

Gas well. Record to Dept. of Mines dated July 5, 1951.

Record to ROT from Mrs. Griffith Aug. 27, 1951. Old File No. 809.

	Top.	Bottom.
Mapletown (Sewickley) Coal	252	- 257
Pittsburgh Coal	320	- 327
Little Dunkard Sand	792	- 812
Gas Sand	996	- 1042
First Salt Sand	1134	- 1209
Second Salt Sand (hole full water, 1300')	1216	- 1371
Little Line	1574	- 1598
Pencil Cave	1598	- 1600
Big Line	1600	- 1674
Big Injun Sand (gas, 1679 and 1772')	1674	- 1804
Total depth		2870
Unable to get below		2648



STATE OF WEST VIRGINIA  
DEPARTMENT OF MINES  
OIL AND GAS DIVISION

809

WELL RECORD

Permit No. MAR-730-A

Oil & Gas Well  
(KIND)


Company Hope Natural Gas Company.  
Address 445 West Main St. Clarksburg, W. Va.  
Farm W.H. Neptune Acres 70  
Location (waters) \_\_\_\_\_  
Well No. 9594 M.P. 256 Elev. 1045  
District Paw Paw County Marion  
The surface of tract is owned in fee by \_\_\_\_\_  
Address \_\_\_\_\_  
Mineral rights are owned by \_\_\_\_\_  
Address \_\_\_\_\_  
Drilling commenced \_\_\_\_\_  
Drilling completed August 1, 1913  
Date Shot \_\_\_\_\_ From \_\_\_\_\_ To \_\_\_\_\_  
With \_\_\_\_\_  
Open Flow \_\_\_\_\_ /10ths Water in \_\_\_\_\_ Inch  
\_\_\_\_\_ /10ths Merc. in \_\_\_\_\_ Inch  
Volume \_\_\_\_\_ Cu. Ft.  
Rock Pressure \_\_\_\_\_ lbs. \_\_\_\_\_ hrs.  
Oil \_\_\_\_\_ bbls., 1st 24 hrs.  
Fresh water \_\_\_\_\_ feet \_\_\_\_\_ feet  
Salt water 1300 feet \_\_\_\_\_ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
16			
13			
10	<u>370</u>	<u>Pulled</u>	Size of
8 1/4	<u>1229</u>	<u>Pulled</u>	
6 5/8	<u>1610</u>	<u>1610</u>	Depth set
5 3/16			
3	<u>1615</u>	<u>1615</u>	Perf. top
2			Perf. bottom
Liners Used			Perf. top
			Perf. bottom

NOT  
CASING CEMENTED \_\_\_\_\_ SIZE \_\_\_\_\_ No. Ft. \_\_\_\_\_ Date \_\_\_\_\_

COAL WAS ENCOUNTERED AT 252 FEET 60 INCHES  
320 FEET 84 INCHES FEET INCHES  
FEET INCHES FEET INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Mapletown coal			252	257			
Pittsburgh Coal			320	327			
Little Dunkard			792	812			
Gas sand			996	1042			
First Salt			1134	1209			
Second Salt			1216	1371	hole full water	1300	
Little Line			1574	1598			
Pencil cave			1598	1600			
Big Line			1600	1674			
Big Injun			1674	1804	gas	1679 1772	
Total depth				2870			
Unable to get below				2648			



(Over)

AUG 27 1951

