

New Location
 Drill Deeper *X*
 Abandonment *X*

MAP NO. 7000, P. 1/2, 1/2, 1/2

Company MOORE NATURAL GAS CO.
 Address CLICKSBURG, W.VA
 Farm B.F. & JNO. BLACKBHERE

STATE OF WEST VIRGINIA
 DEPARTMENT OF MINES
 OIL AND GAS DIVISION
 CHARLESTON

Lincoln District, Marion County, W. Va.

By Hope Natural Gas Co., 405 W. Main St., Clarksburg, W. Va.

Abandoned under permit No.-A?

On 207 acres.

Elevation, 1222' L.

Drilling commenced Nov. 29, 1906; completed Feb. 9, 1907.

Salt water at 1475 and 1495'.

1 1/2" casing, 150' (pulled); 1 1/8", 1007' (pulled); 3/4", 1552' (916' left in);
6 1/2", 2141'; 5 1/2", 2837'; 2" tubing, 3019' (pulled).

Casing was not cemented.

Coal was encountered at 450-455 and 550-558'.

Gas well. Record to Dept. of Mines dated Nov. 6, 1951.

Record to DOT from W. O. Griffith Feb. 29, 1952. Old File No. 823.

	Top.	Bottom.
Coal	450	455
Pittsburgh Coal	550	558
Big Barkard Sand	1007	1107
Gas Sand	1245	1310
First Salt Sand	1335	1390
Second Salt Sand (water, 1475, 1495', hole full)	1455	1600
Little line	1800	1825
Pencil Cave	1825	1830
Big line	1830	1915
Big Injun Sand (gas, 1985, 2026')	1915	2055
Fifty-foot Sand	2475	2528
Stray Sand	2750	2765
Gordon Sand (gas, 2800')	2775	2805
Fourth Sand (gas, 2816')	2814	2835
Fifth Sand (gas, 2953')	2950	2965
Total depth		2965



823

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

WELL RECORD

Permit No. MAR-756-A

Oil or Gas Well (KIND)


Company Hope Natural Gas Company,
 Address 445 West Main St. Clarksburg, W. Va.
 Farm B.F. & John Blackshere Acres 207
 Location (waters) _____
 Well No. 880 Elev. 1222
 District Lincoln County Marion
 The surface of tract is owned in fee by _____
 Address _____
 Mineral rights are owned by _____
 Address _____
 Drilling commenced Nov. 29, 1906
 Drilling completed Feb. 9, 1907
 Date Shot _____ From _____ To _____
 With _____
 Open Flow _____ /10ths Water in _____ Inch
 _____ /10ths Merc. in _____ Inch
 Volume _____ Cu. Ft.
 Rock Pressure _____ lbs. _____ hrs.
 Oil _____ bbls., 1st 24 hrs.
 Fresh water _____ feet _____ feet
 Salt water 1475 1495 feet _____ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer
13	150	Pulled	
10	1007	Pulled	Size of
8 1/4	1552	916	
6 5/8	2141	2141	Depth set
5 3/16	2837	2837	
3			Perf. top
2	3019	Pulled	Perf. bottom
Liners Used			Perf. top
			Perf. bottom

CASING CEMENTED NOT SIZE _____ No. Ft. _____ Date _____

COAL WAS ENCOUNTERED AT 450 FEET 60 INCHES
550 FEET 96 INCHES FEET INCHES
 FEET INCHES FEET INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Coal			450	455			
Pittsburgh Coal			550	558			
Big Dunkard			1007	1107			
Gas sand			1245	1310			
First Salt			1335	1390			
Second Salt			1455	1600	water	1475 1495	hole full
Little Lime			1800	1825			
Pencil cave			1825	1830			
Big Lime			1830	1915			
Big Injun			1915	2055	gas	1985 2026	
Fifty foot			2475	2528			
Stray			2750	2765			
Gordon			2775	2805	gas	2800	
Fourth			2814	2835	gas	2816	
Fifth			2950	2965	gas	2953	
Total depth				2965			



(Over) FEB 29 1952

