

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: August Wendt Operator Well No.: M-1610

LOCATION: Elevation: 1268.15 Quadrangle: Cameron WV, PA
District: Liberty County: Marshall
Latitude: _____ Feet South of 39 Deg. 48 Min. 36.72 Sec.
Longitude: _____ Feet West of -80 Deg. 32 Min. 07.87 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 02/02/2021 or Owner _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 27th day of April, 2021, and the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1173'	706'		
Expandable Cement	706'	Surface		
8 5/8" Casing	1128'	Unknown	1128'	Unknown
10 3/4" Casing	Surface	334'	0'	334'
16" Conductor	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 7th day of May, 2021.

And further deponents saith not

Matthew A. Yearsley

Kevin S. Wright



Sworn and subscribed before me this 17th day of May, 2021

My commission expires: 09/15/22

[Signature]
Notary Public

Affidavit reviewed by the Office of Oil and Gas: [Signature]

Title: inspector

06/11/2021

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES, INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
JOHN D. CUMPSTON ET UX
Lease or Property Owner
488 WENDT LANE. CAMERON, WV 26033
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
CAMERON WV, PA
Well Location
LIBERTY
District
MARSHALL
County
M-1610
Well No.
AUGUST WENDT
Farm

STATE INSPECTOR SUPERVISING PLUGGING Bang Shihp 5-20-21
AFFIDAVIT


STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 27th day of April, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleansed out existing 8 5/8" casing with a 7 7/8 bit from the surface to 1173. Removed 1128' of 8 5/8" casing from the surface to 1128'. Left an unknown amount of 8 5/8" casing in the hole from 1128' to an unknown depth. Cleaned out the existing 10 3/4" casing from the surface to 334'. Continued to clean the hole with a 9 7/8" bit from 334' to the top of the remaining 8 5/8" casing at 1128'. Cleaned a 9 7/8" hole through the Pittsburgh Coal (906' - 912'). Attempted to remove the remaining 10 3/4" casing by pulling 150% of the string weight. All attempts to remove the 10 3/4" casing were unsuccessful. Left 334' of 10 3/4" casing in the hole from the surface to 334'. Left 20' of 16" conductor pipe in hole from the surface to 20'.		8 5/8" Casing	1128'	Unknown
		10 3/4" Casing	0'	334'
		16" Conductor	0'	20'
Cemented the hole from 1173' to surface as follows: From 1173' to 706" with 250 sacks of Thixotropic Cement with Green Dye and gas blocker additive. Tagged top of Thixotropic Cement plug at 706'. From 706' to surface with 330 sacks of Expandable Cement. Cement did circulate at surface. A total of 580 sacks of cement were used to fill the hole from 1173' to surface.				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	906' to 912'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 7th day of May, 2021

And further deponents saith not.



Matthew A. Yearsley
Matthew A. Yearsley
Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 17th day of May, 2021

[Signature] 06/11/2021
Notary Public

My commission expires: 09/15/22

Permit No. 47-051-00034
Well No. M-1610
Latitude: 39° 48' 36.72"N
Longitude: -80° 32' 07.87"W