

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL COMPANY- OHIO VALLEY OPERATIONS

Coal Operator or Owner
RD 4 BOX 425 MOUNDSVILLE, WV 26041
Address

CONSOLIDATION COAL COMPANY- OHIO VALLEY OPERATIONS

Coal Operator or Owner
RD 4 BOX 425 MOUNDSVILLE, WV 26041
Address

THOMAS H. & ROSALIE ELLIOT

Lease or Property Owner
RR 4 BOX 267 CAMERON, WV 26033

Address

RAYMOND RIGGLE

Lease or Property Owner
RR 4 BOX 267 CAMERON, WV 26033
Address

CONSOLIDATION COAL COMPANY- OHIO VALLEY OPERATIONS

Name of Well Operator
RD 4 BOX 425 MOUNDSVILLE, WV 26041

Complete Address
MAJORSVILLE, WV 7.5

Well Location

WEBSTER

District

MARSHALL

County

SGW-91

Well No.

ELLIOT, THOMAS H. & ROSALIE
Farm

STATE INSPECTOR SUPERVISING PLUGGING

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

ROBERT STEEL and KEVIN WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 8th day of March, 2012 and that the well was plugged in the following manner:


Sand or Zone Record Formation	Filling Material	Plugs Used Size & Kind	Casing Pulled	Casing Left In
Cleaned 3 5/8" hole from the surface to 1866'. Ran cement bond log on 4 1/2" casing. Cement bond log indicated that the 4 1/2" casing was cemented in the hole from 1844' to 902'. Removed 4 1/2" casing from the surface to 900'. Left 944' of 4 1/2" casing in the hole from 1844' to 900'. Perforated remaining 4 1/2" casing w/ 6 shots at each of the following depths; 1750', 1650', 1547', 1450', 1343', 1243', 1144', 1049' and 943'. Cut remaining 4 1/2" casing at 1723' and 1530'. Section milled an 11' window in 4 1/2" casing from 1817' to 1828'. Cemented bottom hole from 1866' to 872' with 60 sacks of Expandable Cement w/ a Gas Blocker additive. Simultaneously removed 7" and 8 5/8" casing from the surface to 764' due to a strong cement bond. Left 998' of 7" casing in the hole from 764' to 1762'. Left 534' of 8 5/8" casing in the hole from 764' to 1298'. 7" and 8 5/8" casing bottoms were taken from original well record. Ran cement bond log on 10 3/4" casing. Cement bond log indicated that the 10 3/4" casing was cemented to surface. Left 10 3/4" casing in the hole from the surface to 700'. Section milled a 20' window in 10 3/4" casing from 658' to 678'. Cut remaining 10 3/4" casing at the following depths; 564', 464', 364' and 114'. Section milled 10 3/4" casing through Pittsburgh Coal (665' - 672'). Left 20' of 16" conductor pipe in the hole from 20' to surface		16" Conductor 10 3/4" Casing 8 5/8" Casing 7" Casing 4 1/2" Casing	0' Sec. Milled 764' 764' 900'	20' 680' 534' 998' 944'
Coal Seams		Description of Monument		
<u>PITTSBURGH</u>	665' to 672'	77" of 7" casing w/ company name, well number,		
(Name)		permit number and date cemented stated on 7"		
(Name)		casing .Well marker will be attached to the		
(Name)		cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 27th day of March 2012

And further deponents saith not.

Robert Steel
Robert Steel

Sworn to and subscribed before me this 14th day of April, 2012 Kevin S. Wright
Kevin S. Wright



Jacqueline L. Shriver
Notary Public

Permit No. 47-051-00224-P
Well No. SGW-91

My commission expires:
March 18, 2020

APR 20 2012
05/04/2012