

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: David W. Schrack Operator Well No.: MC110

LOCATION: Elevation: 1135' Quadrangle: Majorsville WV, PA
District: Webster County: Marshall
Latitude: _____ Feet South of 39 Deg. 55 Min. 15.4266 Sec.
Longitude: _____ Feet West of -80 Deg. 36 Min. 23.5296 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources Inc Coal Operator West Virginia Land Resources Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah WV 26554 Monongah WV 26554
Coal Operator _____
Agent David Roddy or Owner _____
Permit Issued Date 11/16/2021

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 16th day of August, 2022, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED		LEFT
Thixotropic Cement	842'	707'	7"	None	890'
Lateral Flow Cement	707'	549' + Coal Laterals	9 5/8"	None	424'
Expandable Cement	549'	Surface	13 3/8"	None	42'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 22nd day of August, 2022.

And further deponents saith not. Kevin S. Wright
[Signature]



Sworn and subscribe before me this 16 day of September, 2022

My commission expires: June 8, 2027
[Signature]
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Strader Gower 9/23/2022 Title: Oil & Gas Inspector

02/17/2023

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
DAVID W SCHRACK
Lease or Property Owner
37 UPPER STULLS RUN ROAD, CAMERON WV 26033
Address

WEST VIRGINIA LAND RESOURCES INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
MAJORSVILLE WV, PA
Well Location
WEBSTER
District
MARSHALL
County
MC110
Well No.
DAVID W SCHRACK
Farm

STATE INSPECTOR SUPERVISING PLUGGING Strader Gower 9/23/2022

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 16th day of August 2022 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Logged production hole with Caliper and Gamma logs to a total depth of 842'. (Set down on hole fill). Attempted to remove 7" casing by pulling 150% of string weight. All attempts were unsuccessful. Set bottom plug from 842' to 707' with 30 sacks of Thixotropic cement. Set 7" packer at 549' and pumped 7,266 gallons of cement or 151% of the total calculated volume into the laterals through the coal seam, access hole to bridge plug, production hole from bottom hole plug to packer until cement was visible at all three laterals. Released 7" packer and cemented the hole from 549' to the surface with 110 sacks of Expandable cement. Cement did circulate at the surface. Left 890' of 7" casing from the surface to 890' with 7" Fiberglass from 608' to 668' through the Pittsburgh Coal Seam (651.5' - 657.3'). Left 424' of 9 5/8" casing from surface to 424'.		7" Steel Casing	0'	830'
		7" Fiberglass Casing	0'	60'
		9 5/8" Steel Casing	0'	424'
		13 3/8" Steel Casing	0'	42'
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>651.5' - 657.3'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 22nd day of August 2022

And further deponents saith not.

Matthew A. Yearsley
Matthew A. Yearsley


Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 14 day of September 2022

Christopher Andrew Willis
Notary Public

My commission expires:

June 8, 2027



Permit No. 47-051-01148
Well No. MC110
Latitude: 39° 55' 15.4266"N
Longitude: -80° 36' 23.5296"W

02/17/2023