




Cameron



Reassigned to: 47-051-01400

~~30356~~

## D. W. McCONAUGHEY NO. 1 (997) WELL.

328A

Cameron District, Marshall County, W. Va.  
 By The Manufacturers Light & Heat Co., 300 Union Trust Bldg., Pittsburgh, Pa.  
 Abandoned under permit No. ....-A1  
 On 200 acres.

Elevation, 1200' L.

Surface owned by Elizabeth McConaughey et al., Cameron, W. Va., and  
 minerals by The Manufacturers Light & Heat Co., 300 Union Trust Bldg.,  
 Pittsburgh, Pa.

Drilling commenced Aug. 20, 1900; completed Nov. 6, 1900.

Conductor, 15"; 13" casing, 210' (pulled); 10", 1146' (pulled); 6", 1920'.

Gas well. Record to Dept. of Mims stamped Oct. 23, 1952.

Record to RCF from Mrs. Griffith Feb. 11, 1953. O.F.No. 407.

	Top.	Bottom.
Waynesburg Coal	479	- ...
Mapletown (Sewickley) Coal	652	- ...
Pittsburgh Coal	762	- ...
Little Dunkard Sand	1195	- 1240
Big Dunkard Sand	1295	- 1345
Gas Sand	1535	- 1565
Salt Sand	1700	- 1822
Salvation Sand	1835	- 1860
Big Linc	1860	- ....
Big Injun Sand	1920	- 2180
Gantz Sand	2645	- ....
50-Foot Sand	2725	- 2743
Cordon Gray Sand (gas at 2772 and 2790')	2770	- ....
Total depth		2798



STATE OF WEST VIRGINIA  
DEPARTMENT OF MINES  
OIL AND GAS DIVISION

Reassigned to: 47-051-01400

407

WELL RECORD

Permit No. MAAS-350-A Oil or Gas Well Gas (KIND)

Company <b>THE MANUFACTURERS LIGHT AND HEAT COMPANY</b>	Casing and Tubing	Used in Drilling	Left in Well	Packers
Address <b>800 Union Trust Bldg., Pittsburgh, Penna.</b>	Size <b>Conductor</b>		<b>15</b>	Kind of Packer
Farm <b>D. W. McConaughey</b> Acres <b>200</b>	<b>16</b>			
Location (waters)	<b>13</b>	<b>210</b>	<b>Pulled</b>	
Well No. <b>1-997</b> Elev. <b>1200'</b>	<b>10</b>	<b>1146</b>	<b>Pulled</b>	Size of
District <b>Cameron</b> County <b>Marshall</b>	<b>8 1/4</b>			Depth set
The surface of tract is owned in fee by <b>Elizabeth McConaughey et al.</b> Address <b>Cameron, W. Va.</b>	<b>6%</b>	<b>1920</b>		
Mineral rights are owned by <b>The Mfg. Light &amp; Heat Company</b> Address <b>800 Union Trust Bldg., Pgh., Pa.</b>	<b>5 3/16</b>			Perf. top
Drilling commenced <b>August 20, 1900</b>	<b>3</b>			Perf. bottom
Drilling completed <b>November 6, 1900</b>	<b>2</b>			Perf. top
Date Shot From To	Liners Used			Perf. bottom
With				

Open Flow /10ths Water in \_\_\_\_\_ Inch  
 \_\_\_\_\_ /10ths Merc. in \_\_\_\_\_ Inch  
 Volume \_\_\_\_\_ Cu. Ft.  
 Rock Pressure \_\_\_\_\_ lbs. \_\_\_\_\_ hrs.  
 Oil \_\_\_\_\_ bbls., 1st 24 hrs.  
 Fresh water \_\_\_\_\_ feet \_\_\_\_\_ feet  
 Salt water \_\_\_\_\_ feet \_\_\_\_\_ feet

CASING CEMENTED \_\_\_\_\_ SIZE \_\_\_\_\_ No. Ft. \_\_\_\_\_ Date \_\_\_\_\_

COAL WAS ENCOUNTERED AT \_\_\_\_\_ FEET \_\_\_\_\_ INCHES  
 \_\_\_\_\_ FEET \_\_\_\_\_ INCHES \_\_\_\_\_ FEET \_\_\_\_\_ INCHES  
 \_\_\_\_\_ FEET \_\_\_\_\_ INCHES \_\_\_\_\_ FEET \_\_\_\_\_ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Waynesburg Coal			470				
Mapletown Coal			652				
Pittsburgh Coal			762				
Little Dunkard			1195	1240			
Big Dunkard			1295	1345			
Gas Sand			1535	1565			
Salt Sand			1700	1822			
Salvation Sand			1835	1860			
Big Lime			1860				
Big Injun			1920	2180			
Gantz Sand			2645				
50 Foot Sand			2725	2743			
Gordon Stray			2770				
TOTAL DEPTH			2798				Gas at 2772 and 2790 feet.

