

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
BRIAN E. & MICHELLE LILLEY
Lease or Property Owner
50 SMITH ROAD CHARITON, MA 01607
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
MOUNDSVILLE, WV 7.5'
Well Location
WEBSTER
District
MARSHALL
County
M-1759
Well No.
LILLEY
Farm

STATE INSPECTOR SUPERVISING PLUGGING Jim Nicholson

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:
JOHN G. CAMPBELL and MATTHEW A. YEARSLEY being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 29th day of May, 2019 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned a 12 1/2" hole from surface to 836'. Tagged solid plug at 836'. Cleaned a 12 1/2" hole through the Pittsburgh Coal Seam from 576.1'-582.8'.		20" Conductor Casing	0	20'
<u>Cemented from 836' to surface as follows:</u> Cemented from 836' to 372' with 370 sacks of Thixotropic Cement with Green Dye. Cemented from 372' to surface with 240 sacks of Expanding Cement. All cement plugs approved by WV DEP Inspector Jim Nickelson. Cement did circulate at surface. Left 20' of 20" conductor casing from 20' to surface.				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>576.1' - 582.8'</u>	<u>77' of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.</u>		

... and that the work of plugging and filling said well was completed on the 7th day of June, 2019


And further deponents saith not.

John G. Campbell
John G. Campbell
Matthew A. Yearsley
Matthew A. Yearsley

Sworn to and subscribed before me this 15th day of June 2019

Carol A. Mayle
Notary Public

My commission expires:



Permit No. 47-051-02167
Well No. M-1759
Latitude: 39° 53' 05.15"N
Longitude: 80° 37' 42.36"W