

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
GLEN KERMIT WENDT
Lease or Property Owner
5704 DRAGON HWY. CAMERON, WV 26033
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
CAMERON WV, PA
Well Location
LIBERTY
District
MARSHALL
County
M-1762
Well No.
AUGUST WENDT
Farm

STATE INSPECTOR SUPERVISING PLUGGING

Bay Alp

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duty sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 28th day of January, 2021 and that the well was plugged in the following manner:

| Sand or Zone Record | Filling Material | Casing/Tubing Size | Casing Pulled | Casing Left In |
|--|--------------------|---|---------------|----------------|
| Formation | | | | |
| Removed 861' of 2 3/8" tubing from the surface to 861'. Cleaned the hole with a 12 1/4" bit from the surface to 68'. Tagged top of existing 10 3/4" casing at 68'. Reduced the hole to 9 7/8" at 68'. Cleaned the hole with a 9 7/8" bit from 68' to 861'. Reduced the hole to 7 7/8" at 861'. Cleaned the hole with a 7 7/8" bit from 855' to 1202'. Tagged a plug at 1202'. Left 152' of 10 3/4" casing in the hole from 68' to 220'. Cleaned a 7 7/8" hole through the Pittsburgh Coal Seam (935' - 941'). Possible junk 2 3/8" tubing remains through coal seam. Left 20' of 16" conductor pipe in the hole from the surface to 20'. | | 2 3/8" Tubing | 861' | 0' |
| | | 10 3/4" Casing | 0' | 152' |
| | | 16" Conductor | 0' | 20' |
| Cemented the hole from 1202' to surface as follows: From 1202' to 735' with 270 sacks of Thixotropic Cement with Green Dye and a gas blocker additive. From 735' to surface with 300 sacks of Expandable Cement. Cement did circulate at surface. A total of 570 sacks of cement were used to cement the hole from 1202' to surface. | | | | |
| Coal Seams | | Description of Monument | | |
| <u>Pittsburgh</u> | <u>935' - 941'</u> | <u>77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.</u> | | |

... and that the work of plugging and filling said well was completed on the 26th day of February, 2021

And further deponents saith not.



Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

Sworn to and subscribed before me this 18th day of Mar, 2021

Thomas J. Sullivan
Notary Public

My commission expires: 09/15/22

Permit No. 47-051-02315
Well No. M-1762
Latitude: 39° 48' 31.51"W
Longitude: -80° 32' 12.61"W

08/06/2021