

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Marshall County Coal Resources Operator Well No.: M-1786

LOCATION: Elevation: 1177.8' Quadrangle: Cameron WV, PA
District: Cameron County: Marshall
Latitude: _____ Feet South of 39 Deg. 49 Min. 43.91 Sec.
Longitude: _____ Feet West of -80 Deg. 32 Min. 10.34 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Coal Operator _____
Agent David Roddy or Owner _____
Permit Issued Date 10/31/2022

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 16th day of December, 2022, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1025'	557'	2 3/8" Tubing - 788' Removed	0'
Expandable Cement	557'	Surface	7" Casing - 0' Removed	Unknown
			16" Conductor - 0' Removed	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 8th day of February, 2023.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright



Sworn and subscribe before me this 14 day of February, 2023

My commission expires: June 8, 2027
Chucky Holcomb
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Shirley Gower Title: 2/21/2023 03/17/2023

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554

Address
WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554

Address
MARSHALL COUNTY COAL RESOURCES
Lease or Property Owner
1626 ENERGY ROAD MOUNDSVILLE, WV 26041

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554

Complete Address
CAMERON WV, PA

Well Location
CAMERON

District
MARSHALL

County
M-1786

Well No.

MARSHALL COUNTY COAL RESOURCES
Farm

STATE INSPECTOR SUPERVISING PLUGGING

Shadrach Gower

02/21/2023

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 16th day of December, 2022 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
	Removed 580' of 2 3/8" tubing from the surface to 580'. Drilled 2 3/8" tubing and cement with a 9 7/8" bit from 580' to 788'. Cleaned a 12 1/4" hole from the surface to 260'. Reduced the hole to 9 7/8" at 260'. Cleaned a 9 7/8" hole from 260' to the top of the existing 7" casing at 844'. Reduced the hole to 6 1/4" at 844'. Cleaned a 6 1/4" hole from 844' to 1025'. Attempted to remove the existing 7" casing from 844' by pulling 150% of the string weight but all attempts were unsuccessful. Left an unknown amount of 7" casing in the hole from 844' to an unknown depth. Cut the remaining 7" casing at 963', 913' and 863'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (757.4' - 763.1'). Left 20' of 16" conductor pipe in the hole from the surface to 20'.	2 3/8" Tubing 7" Casing 16" Conductor	788' 0' 0'	0' Unknown 20'
	<u>Cemented the hole from 1025' back to the surface as follows:</u> From 1025' to 557' with 170 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic Cement plug at 557'. Cemented the hole from 557' to the surface with 295 sacks of Expandable Cement. Cement did circulate at surface. A total of 465 sacks of cement were used to fill the hole from 1025' to the surface.			
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	757.4' - 763.1'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 8th day of February, 2023

And further deponents saith not.

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright


03/17/2023

Sworn to and subscribed before me this 14 day of February 2023

Shadrach Gower
Notary Public

My commission expires:

June 8, 2027



Permit No. 47-051-02473
Well No. M-1786
Latitude: 39° 49' 43.91"N
Longitude: -80° 32' 10.34"W