

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: John Wendt Operator Well No.: M-1789

LOCATION: Elevation: 1355' Quadrangle: Cameron WV, PA
District: Liberty County: Marshall
Latitude: _____ Feet South of 39 Deg. 48 Min. 05.88 Sec.
Longitude: _____ Feet West of -80 Deg. 32 Min. 31.31 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 12/12/2022 or Owner _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 31st day of March, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable Cement w/ Gas Blocker	1406'	1268'	10 3/4" Casing - 0' (multiple cuts)	Unknown
Thixotropic Cement w/ Green Dye	1268'	825'	20" Conductor - 0'	20'
Expandable Cement	825'	Surface		

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 13th day of April, 2023.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright



Sworn and subscribe before me this 24 day of April, 2023

My commission expires: June 8, 2027
Christopher Willis
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Shirley Gower Title: Inspector Oil & Gas

06/23/2023

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

BASIL MCCRACKEN EST. (C/O ANN REEVES)
Lease or Property Owner
324 HORNE RUN RD. AMITY, PA 15311
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
CAMERON WV, PA
Well Location
LIBERTY
District
MARSHALL
County
M-1789
Well No.
JOHN WENDT
Farm

STATE INSPECTOR SUPERVISING PLUGGING Shadrach Gower

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 31st day of March, 2023 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
		10 3/4" Casing	0'	Unknown
		20" Conductor	0'	20'
<p>Cleaned a 12 1/4" hole from the surface to top of existing 10 3/4" casing at 767'. Cleaned a 9 7/8" hole from 767' to 1406'. Cleaned a 9 7/8" hole through Pittsburgh Coal Seam (1025.5' - 1031.5'). Attempts to remove existing 10 3/4" casing from 767' by pulling 150% of the string weight were unsuccessful. Left an unknown amount of 10 3/4" casing in the hole from 767' to an unknown depth. Cut remaining 10 3/4" casing at the following depths; 1231.5', 1181', 1131.5', 1081', 1022', 974' and 924'. The 10 3/4" casing was parted 1014' to 1017' and from 1025' to 1050.5'. Left 20' of 20" conductor pipe in the hole from the surface to 20'.</p> <p>Cemented the hole from 1406' back to the surface as follows: From 1406' to 1268' with 45 sacks of Expandable Cement with a Gas Blocker additive and from 1268' to 825' with 200 sacks of Thixotropic Cement with Green Dye. Tagged top of Thixotropic Cement plug at 825'. Cemented the hole from 825' to the surface with 515 sacks of Expandable Cement. Cement did circulate at surface. A total of 760 sacks of cement were used to fill the hole from 1406' to the surface.</p>				
Coal Seams	Description of Monument			
<u>Pittsburgh</u>	1025.5' - 1031.5'			
	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.			

... and that the work of plugging and filling said well was completed on the 13th day of April, 2023

And further deponents saith not.

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright


Kevin S. Wright

Sworn to and subscribed before me this 24 day of April 2023

06/23/2023

My commission expires:

June 8, 2027



[Signature]
Notary Public

Permit No. 47-051-02477

Well No. M-1789

Latitude: 39° 48' 05.88"N

Longitude: -80° 32' 31.31"W