

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Solomon McCracken Operator Well No.: M-1537

LOCATION: Elevation: 1092.2' Quadrangle: Cameron WV, PA  
District: Cameron County: Marshall  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 49 Min. 34.46 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 32 Min. 32.62 Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
or Owner \_\_\_\_\_  
Permit Issued Date 04/24/2023

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 20th day of July, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable Cement w/ Gas Blocker	1137	885'	8 5/8" Casing - 0'	559' (Placed multiple cut in 8 5/8" csg.)
Thixotropic Cement w/ Green Dye	885'	478'	13 3/8" Conductor - 0'	20'
Expandable Cement	478'	Surface		


Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 17th day of August, 2023.

And further deponents saith not. Matthew A. Yearsley

Kevin S. Wright

Sworn and subscribe before me this 14th day of September, 2023

My commission expires: June 8, 2027 [Signature]  
Notary Public



SEP 23 2023

WV Department of  
Environmental Protection

Affidavit reviewed by the Office of Oil and Gas: [Signature] 9/18/2023 Title: Oil & Gas Inspector

10/20/2023

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
MELISSA JO STONEKING  
Lease or Property Owner  
523 VALLEY GREEN RD. CAMERON, WV 26559  
Address

WEST VIRGINIA LAND RESOURCES INC  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
CAMERON W.VA, PA  
Well Location  
CAMERON  
District  
MARSHALL  
County  
M-1537  
Well No.  
SOLOMON MCCRAKEN  
Farm

STATE INSPECTOR SUPERVISING PLUGGING Shadrach Gossett 9/18/2023

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 20<sup>th</sup> day of July, 2023 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
<b>Formation</b>				
Cleaned a 12 1/4" hole from the surface to 187'. Cleaned a 9 7/8" hole from 187' to the top of the existing 8 5/8" casing at 552'. Cleaned a 6 1/4" hole from 552' to 1137'. Cleaned a 6 1/2" hole through the Pittsburgh Coal Seam (678.2' - 684.4'). A diligent effort was made to remove the 8 5/8" casing from 552' to 1111' but all efforts were unsuccessful. Left 559' of 8 5/8" casing in the hole from 552' to 1111'. Cut the remaining 8 5/8" casing at each of the following depths: 911', 884', 834', 784', 734', 694', 689', 685', 684', 682.5', 681', 679.5', 678', 677', 673', 668', 628' and 578'. Left 20' of 13 3/8" conductor pipe in the hole from the surface to 20'.				
<b>Cemented the hole from 1137' to the surface as follows:</b>				
From 1137' to 885" with 65 sacks of Expandable Cement with a Gas Blocker additive and from 885' to 478' with 145 sacks of Thixotropic Cement with Green Dye. Tagged top of Expandable/Thixotropic Cement plugs at 478'. Cemented the hole from 478' to the surface with 300 sacks of Expandable Cement. Cement did circulate at the surface. A total of 510 sacks of cement were used to fill the hole from 1137' to the surface.				
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	<u>678.2' - 684.4'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 17<sup>th</sup> day of August, 2023

And further deponents saith not.

Matthew A. Yearsley  
Matthew A. Yearsley

Kevin S. Wright  
Kevin S. Wright

Sworn to and subscribed before me this 14<sup>th</sup> day of September, 2023


RECEIVED  
Office of Oil and Gas

Christopher Willis  
Notary Public

SEP 23 2023

My commission expires:

June 8, 2027



Permit No. 47-051-02496  
Well No. M-1537  
Latitude: 39° 49' 34.46"N  
Longitude: -80° 32' 32.62"W

WV Department of  
Environmental Protection

10/20/2023