

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

OCT 15 2019

WV Department of
Environmental Protection

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Henderson Operator Well No.: 5153

LOCATION: Elevation: 1061 Quadrangle: Blacksville
District: Clay County: Monongalia
Latitude: _____ Feet South of _____ Deg. _____ Min. _____ Sec.
Longitude: _____ Feet West of _____ Deg. _____ Min. _____ Sec.

Well Type: OIL _____ GAS

Company Peoples Gas WV, LLS Coal Operator _____
375 North Shore Drive or Owner _____
Pittsburgh, PA 15212
Agent Brett Hoover Coal Operator _____
Permit Issued Date 6/5/19 or Owner _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Roane ss:

Doug Douglass and Ed Burrows, Jr. being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 15 day of July, 2019, and the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
See Attachment A				

Description of monument: Above ground plate welded on 5-1/2" w/ API #, well name, & plug date and that the work of plugging and filling said well was completed on the 9 day of August, 2019.

And further deponents saith not.

Doug Douglass
Ed Burrows, Jr.

Sworn and subscribe before me this 8th day of October, 2019



My commission expires: December 14 2022

David N. Brannon
Notary Public

Digitally signed by Gayne Knitowski, Inspector
Date: 2019.10.10 07:58:46 -04'00'

Affidavit reviewed by the Office of Oil and Gas: _____

Title: Inspector OOG

People's Gas WV LLC			
47-061-00429			
Henderson 5153			
WR-38 Attachment A			
Cement	3,201	2,851	25 sks
Cement	2,851	2,110	15 sks
Cement	2,110	1,840	69 sks
Cement	1,840	1,336	133 sks
Cement	1,336	1,075	57 sks
Cement	1,075	740	143 sks
Cement	740	540	105 sks
Cement	540	482	67 sks
Cement	482	110	275 sks
Cement	110	surface	30 sks
Perforations	3,150 to 2,650 (5) shots every 100'		
Perforations	1,500 to 1,100 (5) shots every 100'		
Csg. Cut	2,083		
Csg. Cut	2,049		
Csg. Cut	1,937		
Csg. Cut	1,823		
Csg. Cut	1,710		
Csg. Cut	1,594		
Csg. Cut	991		
Csg. Cut	900		
Csg. Cut	799		
Csg. Cut	696		
Csg. Cut	594		
Csg. Cut	512		
Csg. Cut	394		
Csg. Cut	294		
Csg. Cut	207		
Csg. (3-1/2")	Pipe Removed 2,083	Left 1,134	
Csg. (5-3/16")	Pipe Removed 1,597	Left	
Csg. (7")	Pipe Removed 0	Left	

RECEIVED
Office of Oil and Gas

▶ OCT 15 2019

WV Department of
Environmental Protection