

Rev (5-01)
WR-38
DATE: 02-21-13

API # 47-6100472P

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Fuhrty, Rose Operator Well No.: E2-S41

LOCATION: Elevation: 1,546' Quadrangle: Grant Town
 District: Clay County: Monongalia
 Latitude: 1.880° Feet South of 39 Deg. 37 Min. 30 Sec.
 Longitude: 8.780° Feet West of 80 Deg. 12 Min. 30 Sec.

Well Type: OIL X GAS _____

Company: Eastern Associated Coal LLC Coal Operator: Eastern Associated Coal LLC
1044 Miracle Run Road or Owner 1044 Miracle Run Road
Fairview, WV 26570 Fairview, WV 26570

Agent: Matthew L. Bonnell Coal Operator _____
 or Owner _____

Permit Issued Date: October 29, 2012

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

KCF Sinc and Eric Dale Chister being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Sam Ward, Oil and Gas Inspector representing the Director, say that said work was commenced on the 12th day of December, 2012, and that the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
	Cleaned out with a 9 3/4" bit to 239'. Cleaned out with a 6 1/2" bit to 2,030'			
Ran logs with Century Wireline Services. There is 7" casing from 240' down to 2100'. The Pittsburgh Coal is 1,081' to 1,086'. The well deviated 18.5' at the coal seam. The 7" casing was shot by Timco Inc below, at, and above the coal seam.				
There is a bottom hole cement plug from 2,030' up to 1,290'. Then they set an expanding cement plug from 1,290' to 980'. Then from 980' to surface it was filled with cement.				
There were 540 sacks of Portland and 105 sacks of expanding cement used to plug the well.				

Description of monument: 4 1/2" Pipe with metal plate, API #, and date plugged and that the work of plugging and filling said well was completed on the 18th day of January, 2013.

And further deponents saith not.

[Signature]
Eric Dale Chister

Sworn and subscribe before me this 21st day of February, 2013
My Commission Expires: July 7, 2017



[Signature]
Notary Public

RECEIVED
Office of Oil & Gas

APR 07 2014

04/11/2014
WV Department of
Environmental Protection