

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Abraham W. Whistler Operator Well No.: 8144

LOCATION: Elevation: 1175.65' Quadrangle: Hundred, WV
District: Battelle County: Monongalia
Latitude: 39.664913 Feet South of 39 Deg. 39 Min. 53.6862 Sec.
Longitude: -80.38956 Feet West of 80 Deg. 23 Min. 22.416 Sec.

Well Type: OIL _____ GAS X

Company	<u>West Virginia Land Resources</u>	Coal Operator	<u>West Virginia Land Resources</u>
	<u>1 Bridge Street</u>	or Owner	<u>1 Bridge Street</u>
	<u>Monongah, WV 26554</u>		<u>Monongah, WV 26554</u>
Agent	<u>David Roddy</u>	Coal Operator	_____
Permit Issued Date	<u>2-19-25</u>	or Owner	_____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew Yearsley and John Campbell being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 30th day of May, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable w/ Gas Blocker	3,240'	2,560'	5/8" Sucker Rod - 3,215'	None
Expandable Cement	2,560'	1,500'	2 3/8" Tubing - 3,226'	None
Expandable Cement	1,500'	1,197'	4 1/2" Casing - 1,500'	Unknown
Thixotropic w/ Green Dye	1,197'	789'	8 5/8" Casing - None	1,098'
Expandable Cement	789'	Surface	10 3/4" Casing - None	Unknown
			16" Conductor - None	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date completed. and that the work of plugging and filling said well was completed on the 19th day of June, 2025.

And further deponents saith not.


Matthew A Yearsley

John Campbell

Sworn and subscribe before me this 16th day of July, 2025

My commission expires: August 13, 2029

Kerri A McCormick
Notary Public



Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554

WEST VIRGINIA LAND RESOURCES
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
KAREN C. & ROBERT D. COPELAND
Lease or Property Owner
PO Box 108 Gorman, WV 26720
Address

WEST VIRGINIA LAND RESOURCES
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
Hundred, WV 7.5'
Well Location
Battelle
District
Monongalia
County
8144
Well No.
ABRAHAM W. WHISTLER
Farm

STATE INSPECTOR SUPERVISING PLUGGING _____ Gayne Knitowski _____

AFFIDAVIT

STATE OF WEST VIRGINIA,


County of MONONGALIA ss:

MATTHEW A. YEARSLEY and JOHN CAMPBELL being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 30th day of May, 2025 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Removed all 3,215' of 5/8" sucker rods from surface to 3,215'. Removed all 3,226' of 2 3/8" tubing from surface to 3,226'. Cleaned a 3 3/4" hole through 4 1/2" casing from surface to 3,240'. Tagged solid plug at 3,240'. Removed 1,500' of 4 1/2" casing from surface to 1,500'. Made diligent effort to remove remaining casing at 1,500' by pulling 150% of string weight. All attempts were unsuccessful. Left unknown amount of 4 1/2" casing in hole from 1,500' to unknown. Perforated remaining 4 1/2" casing at 3,230', 3,130', 3,030', 2,930', 2,830', 2,730'. Cemented hole from 3,240' to 2,560' with 40 sacks of Expandable Cement with Gas Blocker. Additionally tagged cement plug at 2,560'. Perforated 4 1/2" casing from 2,100', 2,000', 1,900', 1,800', 1,700', 1,600'. Cemented from 2,560' to 1,500' w/ 65 sacks of Expandable Cement. Cleaned 7 7/8" hole through 8 5/8" casing from surface to 1,500'. Tagged cement plug at 1500'. A diligent effort to remove 8 5/8" casing from surface to 1,098'. All attempts were unsuccessful. Left 1,098' of 8 5/8" casing from surface to 1,098'. Cut remaining 8 5/8" casing at 1,096.5', 1,046.5', 1,006.5', 1,001.5', 996.5', 994', 991.5', 989', 984', 979', 939', 889'. Pittsburgh Coal Seam was located from 989'-996.5'. Cemented hole from 1500' to surface as follows: from 1,500' to 1,197' with 100 sacks of Expandable cement. From 1197' to 789' with 130 sacks of Thixotropic Cement and Green Dye. From 789' to surface with 190 sacks of Expandable Cement. Cement circulated at surface. Left unknown amount of 10 3/4" casing in well from surface to unknown. Left 20' of 16" conductor from surface to 20'.	5/8" Sucker Rod	3,215'	None	
	2 3/8" Tubing	3,226'	None	
	4 1/2" Casing	1,500'	Unknown	
	8 5/8" Casing	None	1,098'	
	10 3/4" Casing	None	Unknown	
	16" Conductor	None	20'	
Coal Seams		Description of Monument		
Pittsburgh	989' - 996.5'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 19th day of June, 2025

And further deponent(s) doth not.



Matthew A. Yearsley

Matthew A. Yearsley

John Campbell

John Campbell

Sworn to and subscribed before me this 16th day of July 2025

Kerri McCormick
Notary Public

My commission expires: August 13, 2029

Permit No. 47-061-00748
Well No. 8144
Latitude: 39° 39' 53.69"N
Longitude: -80° 23' 22.42"W