


M-7-24-85 P

LATITUDE 39°42'30"

300

V.S. TENNANT



DONALD BROOKOVER

MAYNARD TENNANT  
20.79 AC.

M 3-286

22" POPULAR

LEON WILSON

NIMROD TENNANT

NORTH

00 01 08 E

00 01 08 E

00 01 08 E

00 01 08 E

00 01 08 E

00 01 08 E

00 01 08 E

00 01 08 E

00 01 08 E

00 01 08 E

00 01 08 E

00 01 08 E

00 01 08 E

00 01 08 E

00 01 08 E

00 01 08 E

00 01 08 E

00 01 08 E


00 01 08 E

(+) DENOTES LOCATION OF WELL ON UNITED STATES TOPOGRAPHIC MAPS

FILE NO. \_\_\_\_\_  
 DRAWING NO. \_\_\_\_\_  
 SCALE 1" = 300'  
 MINIMUM DEGREE OF  
 ACCURACY 1 IN 5000  
 PROVEN SOURCE OF  
 ELEVATION COMPANY SURVEY  
TIED INTO THE U.S.G.S. NETWORK

I THE UNDERSIGNED, HEREBY CERTIFY THAT  
 THIS PLAT IS CORRECT TO THE BEST OF MY  
 KNOWLEDGE AND BELIEF AND SHOWS ALL THE  
 INFORMATION REQUIRED BY LAW AND THE REGU-  
 LATIONS ISSUED AND PRESCRIBED BY THE DEPART-  
 MENT OF MINES.

(SIGNED) R. Nelson McCoy  
 R.P.E. \_\_\_\_\_ L.L.S. 110



STATE OF WEST VIRGINIA  
 DEPARTMENT OF MINES  
 OIL AND GAS DIVISION



DATE JANUARY 23, 19 84  
 OPERATOR'S WELL NO. M3-286  
 API WELL NO. \_\_\_\_\_

WELL TYPE: OIL \_\_\_ GAS \_\_\_ LIQUID INJECTION \_\_\_ WASTE DISPOSAL \_\_\_  
 (IF "GAS,") PRODUCTION \_\_\_ STORAGE \_\_\_ DEEP \_\_\_ SHALLOW X ABANDONED X

LOCATION: ELEVATION 1078.00 WATER SHED JAKES RUN  
 DISTRICT CLAY COUNTY MONONGALIA

QUADRANGLE BLACKSVILLE W.V. PA. 4500

SURFACE OWNER MAYNARD TENNANT ACREAGE 20.79

OIL & GAS ROYALTY OWNER UNKNOWN LEASE ACREAGE \_\_\_\_\_

LEASE NO. \_\_\_\_\_

PROPOSED WORK: DRILL \_\_\_ CONVERT \_\_\_ DRILL DEEPER \_\_\_ REDRILL X FRACTURE OR  
 STIMULATE \_\_\_ PLUG OFF OLD FORMATION \_\_\_ PERFORATE NEW  
 FORMATION \_\_\_ OTHER PHYSICAL CHANGE IN WELL (SPECIFY) \_\_\_\_\_

PLUG AND ABANDON \_\_\_ CLEAN OUT AND REPLUG X

TARGET FORMATION NONE ESTIMATED DEPTH \_\_\_\_\_

WELL OPERATOR CONSOLIDATION COAL COMPANY DESIGNATED AGENT ROGER E. DUCKWORTH

ADDRESS P.O. BOX 1314 MORGANTOWN W.V. 26505 ADDRESS P.O. BOX 1314 MORGANTOWN W.V. 26505

AUG 1 1984

FORM IV-6 (8-78)  
 H.T. HALL

COUNTY NAME  
 PERMIT

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Consolidation Coal Company  
Coal Operator or Owner  
P. O. Box 1314 Morgantown, WV 26507 1314  
Address  
Consolidation Coal Company  
Coal Operator or Owner  
P.O. Box 1314, Morgantown, WV 26507-1314  
Address  
Maynard Tennant  
Lease or Property Owner  
Address

Consolidation Coal Company  
Name of Well Operator  
P.D. Box 1314. Morgantown, WV 26507-1314  
Complete Address  
September 06, 19 85  
WELL AND LOCATION  
Clay District  
Monongalia County  
WELL NO. M3 286  
Maynard Tennant Farm

STATE INSPECTOR SUPERVISING PLUGGING Con Ellis, Fairmont, WV 26554

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Calvin C. Lofton and Mark Wright

being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company, well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 23rd day of August, 19 85, and that the well was plugged and filled in the following manner:

| Sand or Zone Record<br>Formation  | Filling Material | Plugs Used<br>Size & Kind | Casing  |                |
|---|------------------|---------------------------|---|----------------|
|   |                  |                           | CSG<br>PULLED                                   | CSG<br>LEFT IN |
| Cleaned out wellbore to 1,923 feet. Pulled 1,922 feet of cable and 1 922 feet of 2 7/8 inch tubing. Pulled 1,624 feet of 5 3/16 feet of casing. Pulled 1,223 feet of 7 inch casing. Pulled 391 feet of 8 inch casing. Set cement plug from 1,923 feet back to 1,450 feet. Ran coal protection string as follows: 412.19 feet of 2 3/8 inch tubing, followed by 755.61 feet of 4 1/2 inch casing. Latch fown plug at 728.61 feet. Float valve at 755.61 feet. Circulated cement to surface as follows: Pumped 600 sacks of poz mix followed by 425 sacks of expanding cement. Displaced cement to 728.61 feet with water. Let set. Bailed dry. Total plug 1,167.80 feet. |                  |                           |   |                |
| Coal Seams  |                  |                           | Description of Monument                         |                |
| (Name) Pittsburgh 605 feet to 613 feet.   |                  |                           | 5 feet of 4 1/2 inch casing with plaque stating |                |
| (Name)  |                  |                           | Consol M3-286                                   |                |
| (Name)  |                  |                           | 47-061-0796-P                                   |                |

and that the work of plugging and filling said well was completed on the 30th day of August, 19 85.

And further deponents saith not.

Sworn to and subscribed before me this 9th day of September, 19 85.

*Calvin C. Lofton*  
*Mark Wright*  
Notary Public

My commission expires:  
September 8, 1988

Permit No. 47 061 0796-P