

Mailed 7/28/89

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Consolidation Coal Company  
Coal Operator or Owner  
P. O. Box 1314, Morgantown, WV 26507-1314  
Address

---

Coal Operator or Owner  
Address  
Vernon Santee Ruth Santee  
Lease or Property Owner  
Route 1, Box 76-A, Fairview, WV 26570  
Address

Consolidation Coal Company  
Name of Well Operator  
P. O. Box 1314, Morgantown, WV 26507-1314  
Complete Address  
August 19, 19 89

---

WELL AND LOCATION  
Battelle District  
Monongalia County  
WELL NO. 3833  
Vernor Santee Farm Farm

STATE INSPECTOR SUPERVISING PLUGGING Don Ellis, Fairmont, WV

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Harrison

ss:

Calvin C. Lofton and George R. Gore

being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company, well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 1st day of August, 19 89, and that the well was plugged and filled in the following manner:

Sand or Zone Record Formation	Filling Material	Plugs Used Size & Kind	Casing	
			CSG PULLED	CSO LEFT IN
Cleaned 9 7/8" hole to 667'. Reduced hole to 7 7/8" at 667'. Cleaned 7 7/8" hole to 1,336'. Pulled 8 5/8" casing from 667' to 1,004'.	8 5/8" casing left in hole from 1,004' to 1,243'. Drilled 7 7/8" hole thru Pittsburgh Coal from 738' to 746'. Ran coal protection string as follows 311.23' of 2 3/8" tubing followed by 936.34' of 4 1/2" casing. Latch down plug at 915.16'. Float valve at 936.34'. Swedge at 937.34'. Circulated cement to surface as follows: Pumped 750 sacks of poz mix followed by 250 sacks of expanding cement. Used 1,000 gallons of mud flush. Displaced cement to 915.16 feet with water. Let set, bailed dry.			
TOTAL DEPTH: 1,247.57 FEET				
Coal Seams	Description of Monument			
(Name) Pittsburgh	733 feet to 746 feet	5 feet of 4 1/2" casing with plaque stating: Consol WV #3833 #47-061-0920-P		

RECEIVED  
SEP 29 1989


DIVISION OF OIL & GAS  
DEPARTMENT OF ENERGY

MAJ 10/2/89

and that the work of plugging and filling said well was completed on the 7th day of August, 19 89.

And further deponents saith not.

Calvin C. Lofton  
George R. Gore  
Charlitta Heater  
Notary Public



June 29, 1999

Permit No. 47-061-0920-P

N. 02020. 0920-P